



08.29.2025

Structural Calculations for

SOUTHEAST ALASKA REGIONAL HEALTH CONSORTIUM


WRANGELL STAFF HOUSING

SINGLE BEDROOM DUPLEX (SHED ROOF)

1064 Zimovia Hwy, Wrangell AK 99929


Prepared by:
Asrade Mengstu PE

Reviewed by:
Kevin Feldman PE



DESIGN LOADS AND CRITERIA

- 1) GRAVITY LOADS:
 - a) ROOF LOADS:
 1. ROOF DEAD LOAD: 18 psf
 2. ROOF LIVE LOAD: 20 psf
 - b) FLOOR LOADS:
 1. FLOOR LIVE LOAD: 40 psf (RESIDENTIAL — ONE- AND TWO-FAMILY DWELLINGS — ALL OTHER AREAS EXCEPT STAIRS)
 2. FLOOR LIVE LOAD: 60 psf (BALCONIES AND DECKS)
 - c) SLABS ON GRADE:
 1. SLABS ON GRADE LIVE LOAD: 40 psf
- 2) HANDRAIL AND GUARDRAIL SYSTEM LOADS:
 - a) CONCENTRATED LOAD: 200 lb (HANDRAIL OR TOP RAIL)
 - b) CONCENTRATED LOAD: 50 lb (INTERMEDIATE RAIL)
 - c) LINEAR LOAD: 50 lb/ft (HANDRAIL OR TOP RAIL)
- 3) SNOW LOADS:
 - a) GROUND SNOW LOAD: $P_g = 60$ psf, $I_s = 1.00$, $C_e = 1.0$, $C_t = 1.0$, $C_s = 1.0$
 - b) FLAT ROOF SNOW LOAD: $P_f = 42$ psf UNIFORM + DRIFT
- 4) WIND CRITERIA:
 - a) 3-SEC PEAK GUST WIND SPEED = 139 mph
 - b) RISK CATEGORY = II
 - c) $I_w = 1.00$
 - d) EXPOSURE = D
 - e) INTERNAL PRESSURE COEFFICIENT (GC_{pi}): ± 0.18
 - f) EXTERNAL ROOF COMPONENTS & CLADDING: 75 psf MINIMUM (ULTIMATE)
 - g) EXTERNAL WALL COMPONENTS & CLADDING: 80 psf MINIMUM (ULTIMATE)
 - h) STEEL ROOF JOIST NET UPLIFT - PERIMETER 20 FT: 50 psf MINIMUM (ULTIMATE)
 - i) INTERSTORY DRIFT LIMIT = $1/400$
- 5) SEISMIC CRITERIA:
 - a) $SS = 0.249$ g / $S_1 = 0.254$ g MAPPED MCER VALUES
 - b) RISK CATEGORY = II
 - c) PROJECT SITE CLASS = B
 - d) $I_e = 1.00$
 - e) $SDS = 0.149$ g / $SD_1 = 0.136$ g DESIGN RESPONSE COEFFICIENT
 - f) SEISMIC DESIGN CATEGORY = C
 - g) ANALYSIS PROCEDURE: EQUIVALENT LATERAL FORCE PROCEDURE
 - h) SEISMIC FORCE-RESISTING SYSTEM: BEARING WALL SYSTEMS: LIGHT-FRAME (WOOD) WALLS SHEATHED WITH WOOD STRUCTURAL PANELS RATED FOR SHEAR RESISTANCE, $R = 6.5$
 - i) REDUNDANCY FACTOR: PLAN N-S $RHO = 1.3$ / PLAN E-W $RHO = 1.3$
 - j) SEISMIC RESPONSE COEFFICIENT $C_s = 0.030$
 - k) SEISMIC BASE SHEAR $V = 1.7$ kips (ULTIMATE)
 - l) ALLOWABLE STORY DRIFT $\Delta = 0.020h_{sx}$
- 6) FOOTING BEARING PRESSURE: 3000 psf ON APPROVED SUBGRADE, SEE SECTION FOUNDATIONS
- 7) SOIL FRICTION COEFFICIENT: 0.4
- 8) LATERAL SOIL PRESSURE:
 - a) ACTIVE EQUIVALENT FLUID PRESSURE: 35 pcf
 - b) AT-REST EQUIVALENT FLUID PRESSURE: 55 pcf
 - c) PASSIVE EQUIVALENT FLUID PRESSURE: 400 pcf
- 9) FROST DEPTH: 32 INCHES TOP OF FOOTING



1
S102

ROOF FRAMING PLAN

1/4" = 1'-0"



NORTH REF

Snow Loads : ASCE 7- 16

Nominal Snow Forces

Roof slope = 3.6 deg
 Horiz. eave to ridge dist (W) = 35.0 ft
 Roof length parallel to ridge (L) = 57.0 ft

Type of Roof Monoslope
 Ground Snow Load Pg = 60.0 psf
 Risk Category = II
 Importance Factor I = 1.0
 Thermal Factor Ct = 1.00
 Exposure Factor Ce = 1.0

Pf = $0.7 \cdot Ce \cdot Ct \cdot I \cdot Pg$ = 42.0 psf
 Unobstructed Slippery Surface no

Sloped-roof Factor Cs = 1.00
 Balanced Snow Load = **42.0 psf**


Rain on Snow Surcharge Angle 0.70 deg
 Code Maximum Rain Surcharge 5.0 psf
 Rain on Snow Surcharge = 0.0 psf
 Ps plus rain surcharge = 42.0 psf
 Minimum Snow Load Pm = 20.0 psf

Uniform Roof Design Snow Load = **42.0 psf**

Near ground level surface balanced snow load = **60.0 psf**

NOTE: Alternate spans of continuous beams shall be loaded with half the design roof snow load so as to produce the greatest possible effect - see code for loading diagrams and exceptions for gable roofs..

Left cantilever exceeds the maximum braced cantilever length of 5'.



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	697 @ 19' 5 1/2"	1156 (1.75")	Passed (60%)	1.15	1.0 D + 1.0 S (Alt Spans)
Shear (lbs)	810 @ 5' 11 1/2"	1903	Passed (43%)	1.15	1.0 D + 1.0 S (All Spans)
Moment (Ft-lbs)	-1872 @ 5' 8 3/4"	3273	Passed (57%)	1.15	1.0 D + 1.0 S (All Spans)
Live Load Defl. (in)	0.205 @ 12' 10"	0.459	Passed (L/805)	--	1.0 D + 1.0 S (Alt Spans)
Total Load Defl. (in)	0.263 @ 12' 10 15/16"	0.688	Passed (L/629)	--	1.0 D + 1.0 S (Alt Spans)

 Member Length : 19' 6 11/16"
 System : Roof
 Member Type : Joist
 Building Use : Residential
 Building Code : IBC 2021
 Design Methodology : ASD
 Member Pitch : 0.75/12

- Deflection criteria: LL (L/360) and TL (L/240).
- Overhang deflection criteria: LL (2L/360) and TL (2L/240).
- Moment capacity over cantilever support 1 has been reduced by 25% to lessen the effects of buckling.
- Allowed moment does not reflect the adjustment for the beam stability factor.

Supports	Bearing Length			Loads to Supports (lbs)				Accessories	Details
	Total	Available	Required	Dead	Roof Live	Snow	Factored		
1 - Beveled Plate - SPF	5.50"	5.50"	3.50"	414	552	1158	1573	Blocking	R1
2 - Hanger on 11 7/8" GLB beam	5.50"	Hanger ¹	1.75" / - ²	184	269	565	749	See note ¹	H5

- Blocking Panels are assumed to carry no loads applied directly above them and the full load is applied to the member being designed.
- At hanger supports, the Total Bearing dimension is equal to the width of the material that is supporting the hanger
- ¹ See Connector grid below for additional information and/or requirements.
- ² Required Bearing Length / Required Bearing Length with Web Stiffeners

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	5' o/c	
Bottom Edge (Lu)	5' 5" o/c	

- TJI joists are only analyzed using Maximum Allowable bracing solutions.
- Maximum allowable bracing intervals based on applied load.
- Dimensions for lateral bracing intervals are measured along the length of the member for sloped conditions.

Connector: Simpson Strong-Tie

Support	Model	Seat Length	Top Fasteners	Face Fasteners	Member Fasteners	Accessories
2 - Face Mount Hanger	LSSR2.1Z	1.88"	N/A	14-10dx2.5	12-10dx1.5	Web Stiffeners

- Refer to manufacturer notes and instructions for proper installation and use of all connectors.

Vertical Load	Location	Spacing	Dead (0.90)	Roof Live (1.25)	Snow (1.15)	Comments
1 - Uniform (PSF)	0 to 19' 11"	24"	15.0	20.0	42.0	Default Load

ForteWEB Software Operator	Job Notes
Asrade Mengstu Cushing Terrell (406) 500-3544 asrademengstu@cushingterrell.com	

Weyerhaeuser Notes


Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to www.weyerhaeuser.com/woodproducts/document-library.

The product application, input design loads, dimensions and support information have been provided by ForteWEB Software Operator


ForteWEB Software Operator	Job Notes
Asrade Mengstu Cushing Terrell (406) 500-3544 asrademengstu@cushingterrell.com	



LSTA24 (Simpson Strong-Tie or USP Structural Connectors) strap with twelve 10d (0.148 x 1 1/2") nails required at H5S with slopes greater than 3:12



Shear blocking:
1 1/8" TJ® Rim Board (with depths ≤ 16"),
1 1/4" or 1 1/2" TimberStrand® LSL
or TJI® joist.



ForteWEB Software Operator	Job Notes
Asrade Mengstu Cushing Terrell (406) 500-3544 asrademengstu@cushingterrell.com	



8/29/2025 11:14:47 PM UTC


ForteWEB v3.9

File Name: SEARHC Wrangell 1bdmDupShed

Right cantilever exceeds the maximum braced cantilever length of 5'.

FAILED

**OK, PLY APPLIED TO
UNDERSIDE OF TJI
CANTILEVER**



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	1577 @ 14' 2 1/4"	2956 (5.25")	Passed (53%)	1.15	1.0 D + 1.0 S (All Spans)
Shear (lbs)	814 @ 13' 11 1/2"	1903	Passed (43%)	1.15	1.0 D + 1.0 S (All Spans)
Moment (Ft-lbs)	-1872 @ 14' 2 1/4"	3273	Passed (57%)	1.15	1.0 D + 1.0 S (All Spans)
Live Load Defl. (in)	0.210 @ 7' 1/2"	0.461	Passed (L/790)	--	1.0 D + 1.0 S (Alt Spans)
Total Load Defl. (in)	0.269 @ 6' 11 9/16"	0.692	Passed (L/616)	--	1.0 D + 1.0 S (Alt Spans)

- Deflection criteria: LL (L/360) and TL (L/240).
- Overhang deflection criteria: LL (2L/360) and TL (2L/240).
- Moment capacity over cantilever support 2 has been reduced by 25% to lessen the effects of buckling.
- Allowed moment does not reflect the adjustment for the beam stability factor.

Member Length : 20' 3/16"
System : Roof
Member Type : Joist
Building Use : Residential
Building Code : IBC 2021
Design Methodology : ASD
Member Pitch : 0.75/12

Supports	Bearing Length			Loads to Supports (lbs)				Accessories	Details
	Total	Available	Required	Dead	Roof Live	Snow	Factored		
1 - Beveled Plate - DF	5.50"	5.50"	1.75"	183	267	562	745	Blocking	R1
2 - Beveled Plate - DF	5.50"	5.50"	3.50"	416	553	1161	1577	Blocking	R1

• Blocking Panels are assumed to carry no loads applied directly above them and the full load is applied to the member being designed.

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	5' o/c	
Bottom Edge (Lu)	5' 5" o/c	

- TJI joists are only analyzed using Maximum Allowable bracing solutions.
- Maximum allowable bracing intervals based on applied load.
- Dimensions for lateral bracing intervals are measured along the length of the member for sloped conditions.

Vertical Load	Location	Spacing	Dead (0.90)	Roof Live (1.25)	Snow (1.15)	Comments
1 - Uniform (PSF)	0 to 19' 11"	24"	15.0	20.0	42.0	Default Load

Weyerhaeuser Notes



Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to www.weyerhaeuser.com/woodproducts/document-library.

The product application, input design loads, dimensions and support information have been provided by ForteWEB Software Operator

ForteWEB Software Operator	Job Notes
Asrade Mengstu Cushing Terrell (406) 500-3544 asrademengstu@cushingterrell.com	

Shear blocking:

1 1/8" TJ® Rim Board (with depths ≤ 16"),
 1 1/4" or 1 1/2" TimberStrand® LSL
 or TJI® joist.



ForteWEB Software Operator	Job Notes
Asrade Mengstu Cushing Terrell (406) 500-3544 asrademengstu@cushingterrell.com	




8/29/2025 11:14:53 PM UTC

ForteWEB v3.9

File Name: SEARHC Wrangell 1bdmDupShed

Roof, Roof: Joist RJ3

1 piece(s) 11 7/8" TJI® 210 @ 24" OC



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	1020 @ 4 1/2"	1679 (3.50")	Passed (61%)	1.15	1.0 D + 1.0 S (Alt Spans)
Shear (lbs)	967 @ 5 1/2"	1903	Passed (51%)	1.15	1.0 D + 1.0 S (Alt Spans)
Moment (Ft-lbs)	4184 @ 8' 11 5/16"	4364	Passed (96%)	1.15	1.0 D + 1.0 S (Alt Spans)
Live Load Defl. (in)	0.587 @ 9' 1/16"	0.578	Passed (L/355)	--	1.0 D + 1.0 S (Alt Spans)
Total Load Defl. (in)	0.793 @ 9'	0.867	Passed (L/262)	--	1.0 D + 1.0 S (Alt Spans)

Member Length : 20' 3/16"
System : Roof
Member Type : Joist
Building Use : Residential
Building Code : IBC 2021
Design Methodology : ASD
Member Pitch : 0.75/12

- Deflection criteria: LL (L/360) and TL (L/240).
- Overhang deflection criteria: LL (2L/360) and TL (2L/240).
- Upward deflection on right cantilever exceeds overhang deflection criteria.
- Allowed moment does not reflect the adjustment for the beam stability factor.
- Permanent bracing at third points in the back span or a direct applied ceiling over the entire back span length is required at the right span of the member. See literature detail (PB1) for clarification.

Supports	Bearing Length			Loads to Supports (lbs)				Accessories	Details
	Total	Available	Required	Dead	Roof Live	Snow	Factored		
1 - Beveled Plate - DF	5.50"	5.50"	1.75"	267	358	753	1020	Blocking	R1
2 - Beveled Plate - DF	5.50"	5.50"	3.50"	332	441	926	1258	Blocking	R1

Blocking Panels are assumed to carry no loads applied directly above them and the full load is applied to the member being designed.

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	3' 5" o/c	
Bottom Edge (Lu)	8' 8" o/c	

- TJI joists are only analyzed using Maximum Allowable bracing solutions.
- Maximum allowable bracing intervals based on applied load.
- Dimensions for lateral bracing intervals are measured along the length of the member for sloped conditions.

Vertical Load	Location	Spacing	Dead (0.90)	Roof Live (1.25)	Snow (1.15)	Comments
1 - Uniform (PSF)	0 to 19' 11"	24"	15.0	20.0	42.0	Default Load


Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to www.weyerhaeuser.com/woodproducts/document-library.

The product application, input design loads, dimensions and support information have been provided by ForteWEB Software Operator

ForteWEB Software Operator	Job Notes
Asrade Mengstu Cushing Terrell (406) 500-3544 asrademengstu@cushingterrell.com	

Apply subfloor adhesive to all contact surfaces




Option #1:
TJI® joist blocking with end blocks installed at $\frac{1}{3}$ joist-span locations (8' max typical) using two 8d (0.113" x 2 $\frac{1}{2}$ ") nails or 2 $\frac{1}{2}$ " screws

Option #2:
2x_ strapping installed at $\frac{1}{3}$ joist-span locations using two 2 $\frac{1}{2}$ " screws per joist, typical

Option #3:
Directly applied ceiling

Shear blocking:
1 $\frac{1}{8}$ " TJ® Rim Board (with depths ≤ 16 "),
1 $\frac{1}{4}$ " or 1 $\frac{1}{2}$ " TimberStrand® LSL
or TJI® joist.



PB1

When specified on the layout, one of the bracing options above is required

R1

R1W

ForteWEB Software Operator	Job Notes
Asrade Mengstu Cushing Terrell (406) 500-3544 asrademengstu@cushingterrell.com	




8/29/2025 11:14:58 PM UTC

ForteWEB v3.9

File Name: SEARHC Wrangell 1bdrmDupShed

Roof, Roof Beam RB1

1 piece(s) 3 1/2" x 11 7/8" 24F-V8 DF Glulam



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	7385 @ 2' 2 3/4"	12513 (5.50")	Passed (59%)	--	1.0 D + 1.0 S (All Spans)
Shear (lbs)	4166 @ 3' 5 3/8"	8444	Passed (49%)	1.15	1.0 D + 1.0 S (All Spans)
Pos Moment (Ft-lbs)	14469 @ 8' 10 1/2"	18920	Passed (76%)	1.15	1.0 D + 1.0 S (Alt Spans)
Neg Moment (Ft-lbs)	-3268 @ 2' 2 3/4"	18920	Passed (17%)	1.15	1.0 D + 1.0 S (All Spans)
Live Load Defl. (in)	0.358 @ 8' 8 1/2"	0.643	Passed (L/430)	--	1.0 D + 1.0 S (Alt Spans)
Total Load Defl. (in)	0.482 @ 8' 8 3/4"	0.857	Passed (L/320)	--	1.0 D + 1.0 S (Alt Spans)

Member Length : 15' 5"
System : Roof
Member Type : Drop Beam
Building Use : Residential
Building Code : IBC 2021
Design Methodology : ASD
Member Pitch : 0/12

- Deflection criteria: LL (L/240) and TL (L/180).
- Overhang deflection criteria: LL (2L/240) and TL (2L/180).
- Allowed moment does not reflect the adjustment for the beam stability factor.
- Volume factor of 1.00 was calculated for positive bending using length L = 12' 5".
- Volume factor of 1.00 was calculated for negative bending using length L = 2' 10 7/8".
- The effects of positive or negative camber have not been accounted for when calculating deflection.
- Applicable calculations are based on NDS.

Supports	Bearing Length			Loads to Supports (lbs)				Accessories
	Total	Available	Required	Dead	Roof Live	Snow	Factored	
1 - Column - DF	5.50"	5.50"	3.25"	2063	2534	5322	7385	Blocking
2 - Column - DF	5.50"	5.50"	2.16"	1310	1715	3602	4913	Blocking

- Blocking Panels are assumed to carry no loads applied directly above them and the full load is applied to the member being designed.

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	15' 5" o/c	
Bottom Edge (Lu)	15' 5" o/c	

- Maximum allowable bracing intervals based on applied load.

Vertical Loads	Location (Side)	Tributary Width	Dead (0.90)	Roof Live (1.25)	Snow (1.15)	Comments
0 - Self Weight (PLF)	0 to 15' 5"	N/A	10.1	--	--	
1 - Uniform (PSF)	0 to 15' 5" (Front)	13'	15.0	20.0	42.0	Default Load
2 - Point (lb)	0 (Front)	N/A	211	199	418	Linked from: Roof Beam RB2, Support 2

- Side loads are assumed to not induce cross-grain tension.

Weyerhaeuser Notes


Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to www.weyerhaeuser.com/woodproducts/document-library.

The product application, input design loads, dimensions and support information have been provided by ForteWEB Software Operator

ForteWEB Software Operator	Job Notes
Asrade Mengstu Cushing Terrell (406) 500-3544 asrademengstu@cushingterrell.com	

Roof, Roof Beam RB2

1 piece(s) 1 3/4" x 11 7/8" 1.55E TimberStrand® LSL



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	604 @ 1 3/4"	2363 (1.50")	Passed (26%)	--	1.0 D + 1.0 S (All Spans)
Shear (lbs)	541 @ 1' 1 5/8"	4939	Passed (11%)	1.15	1.0 D + 1.0 S (All Spans)
Moment (Ft-lbs)	2867 @ 9' 7 3/4"	9173	Passed (31%)	1.15	1.0 D + 1.0 S (All Spans)
Live Load Defl. (in)	0.340 @ 9' 7 3/4"	0.952	Passed (L/672)	--	1.0 D + 1.0 S (All Spans)
Total Load Defl. (in)	0.515 @ 9' 7 3/4"	1.269	Passed (L/444)	--	1.0 D + 1.0 S (All Spans)

- Deflection criteria: LL (L/240) and TL (L/180).
- Allowed moment does not reflect the adjustment for the beam stability factor.

Member Length : 19' 1 3/16"
System : Roof
Member Type : Drop Beam
Building Use : Residential
Building Code : IBC 2021
Design Methodology : ASD
Member Pitch : 0.75/12

Supports	Bearing Length			Loads to Supports (lbs)				Accessories
	Total	Available	Required	Dead	Roof Live	Snow	Factored	
1 - Hanger on 11 7/8" DF beam	1.75"	Hanger ¹	1.50"	207	193	405	612	See note ¹
2 - Hanger on 11 7/8" GLB beam	5.50"	Hanger ¹	1.50"	211	199	418	630	See note ¹

- At hanger supports, the Total Bearing dimension is equal to the width of the material that is supporting the hanger
- ¹ See Connector grid below for additional information and/or requirements.

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	12' 9" o/c	
Bottom Edge (Lu)	19' o/c	

- Maximum allowable bracing intervals based on applied load.
- Dimensions for lateral bracing intervals are measured along the length of the member for sloped conditions.

Connector: Simpson Strong-Tie						
Support	Model	Seat Length	Top Fasteners	Face Fasteners	Member Fasteners	Accessories
1 - Face Mount Hanger	U14X SLU3	2.00"	N/A	14-10dx1.5	6-10dx1.5	
2 - Face Mount Hanger	LSSR1.81Z	1.88"	N/A	14-10dx2.5	12-10dx1.5	

- Refer to manufacturer notes and instructions for proper installation and use of all connectors.

Vertical Loads	Location (Side)	Tributary Width	Dead (0.90)	Roof Live (1.25)	Snow (1.15)	Comments
0 - Self Weight (PLF)	1 3/4" to 19' 1 3/4"	N/A	6.5	--	--	
1 - Uniform (PSF)	0 to 19' 7 1/4"	1'	15.0	20.0	42.0	Default Load


- Side loads are assumed to not induce cross-grain tension.

Weyerhaeuser Notes
Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to www.weyerhaeuser.com/woodproducts/document-library .
The product application, input design loads, dimensions and support information have been provided by ForteWEB Software Operator

ForteWEB Software Operator	Job Notes
Asrade Mengstu Cushing Terrell (406) 500-3544 asrademengstu@cushingterrell.com	

Roof, Roof Beam RB3

1 piece(s) 1 3/4" x 11 7/8" 1.55E TimberStrand® LSL



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	1131 @ 15' 11 1/2"	2363 (1.50")	Passed (48%)	--	1.0 D + 1.0 S (Alt Spans)
Shear (lbs)	1134 @ 3' 5 3/8"	4939	Passed (23%)	1.15	1.0 D + 1.0 S (All Spans)
Moment (Ft-lbs)	3605 @ 9' 7"	9173	Passed (39%)	1.15	1.0 D + 1.0 S (Alt Spans)
Live Load Defl. (in)	0.255 @ 9' 2 11/16"	0.686	Passed (L/647)	--	1.0 D + 1.0 S (Alt Spans)
Total Load Defl. (in)	0.341 @ 9' 3 7/16"	0.915	Passed (L/484)	--	1.0 D + 1.0 S (Alt Spans)

- Deflection criteria: LL (L/240) and TL (L/180).
- Overhang deflection criteria: LL (2L/240) and TL (2L/180).
- Allowed moment does not reflect the adjustment for the beam stability factor.

Member Length : 15' 11 1/2"
System : Roof
Member Type : Drop Beam
Building Use : Residential
Building Code : IBC 2021
Design Methodology : ASD
Member Pitch : 0/12

Supports	Bearing Length			Loads to Supports (lbs)				Accessories
	Total	Available	Required	Dead	Roof Live	Snow	Factored	
1 - Beam - DF	5.50"	5.50"	2.16"	718	781	1639	2358	None
2 - Hanger on 11 7/8" GLB beam	5.50"	Hanger ¹	1.50"	331	418	878	1210	See note ¹

• At hanger supports, the Total Bearing dimension is equal to the width of the material that is supporting the hanger

• ¹ See Connector grid below for additional information and/or requirements.

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	9' 8" o/c	
Bottom Edge (Lu)	16' o/c	

• Maximum allowable bracing intervals based on applied load.

Connector: Simpson Strong-Tie

Support	Model	Seat Length	Top Fasteners	Face Fasteners	Member Fasteners	Accessories
2 - Face Mount Hanger	IUS1.81/11.88	2.00"	N/A	10-10d	2-10dx1.5	

• Refer to manufacturer notes and instructions for proper installation and use of all connectors.

Vertical Loads	Location (Side)	Tributary Width	Dead (0.90)	Roof Live (1.25)	Snow (1.15)	Comments
0 - Self Weight (PLF)	0 to 15' 11 1/2"	N/A	6.5	--	--	
1 - Uniform (PSF)	0 to 16' 5" (Front)	3'	15.0	20.0	42.0	Default Load
2 - Point (lb)	0 (Front)	N/A	207	193	405	Linked from: Roof Beam RB2, Support 1

• Side loads are assumed to not induce cross-grain tension.

Weyerhaeuser Notes


Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to www.weyerhaeuser.com/woodproducts/document-library.

The product application, input design loads, dimensions and support information have been provided by ForteWEB Software Operator

ForteWEB Software Operator	Job Notes
Asrade Mengstu Cushing Terrell (406) 500-3544 asrademengstu@cushingterrell.com	

Roof, Roof Beam RB4

1 piece(s) 3 1/2" x 11 7/8" 24F-V8 DF Glulam



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	3966 @ 2' 2 3/4"	12031 (5.50")	Passed (33%)	--	1.0 D + 1.0 S (Adj Spans)
Shear (lbs)	2482 @ 1' 1/8"	8444	Passed (29%)	1.15	1.0 D + 1.0 S (All Spans)
Pos Moment (Ft-lbs)	2189 @ 14' 5 3/4"	18920	Passed (12%)	1.15	1.0 D + 1.0 S (Alt Spans)
Neg Moment (Ft-lbs)	-5562 @ 2' 2 3/4"	18920	Passed (29%)	1.15	1.0 D + 1.0 S (All Spans)
Live Load Defl. (in)	0.040 @ 0	0.223	Passed (2L/999+)	--	1.0 D + 1.0 S (Alt Spans)
Total Load Defl. (in)	0.058 @ 0	0.297	Passed (2L/924)	--	1.0 D + 1.0 S (Alt Spans)

Member Length : 20' 5"
System : Roof
Member Type : Drop Beam
Building Use : Residential
Building Code : IBC 2021
Design Methodology : ASD
Member Pitch : 0/12

- Deflection criteria: LL (L/240) and TL (L/180).
- Overhang deflection criteria: LL (2L/240) and TL (2L/180).
- Allowed moment does not reflect the adjustment for the beam stability factor.
- Volume factor of 1.00 was calculated for positive bending using length L = 11' 10 9/16".
- Volume factor of 1.00 was calculated for negative bending using length L = 8' 6 13/16".
- The effects of positive or negative camber have not been accounted for when calculating deflection.
- Applicable calculations are based on NDS.

Supports	Bearing Length			Loads to Supports (lbs)				Accessories
	Total	Available	Required	Dead	Roof Live	Snow	Factored	
1 - Beam - DF	5.50"	5.50"	1.81"	1159	1337	2807	3966	None
2 - Column - DF	5.50"	5.50"	1.50"	141	342/-140	720/-294	860/-154	Blocking
3 - Hanger on 11 7/8" GLB beam	5.50"	Hanger ¹	1.50"	250	257	539	789	See note ¹

- Blocking Panels are assumed to carry no loads applied directly above them and the full load is applied to the member being designed.
- At hanger supports, the Total Bearing dimension is equal to the width of the material that is supporting the hanger
- ¹ See Connector grid below for additional information and/or requirements.

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	20' 5" o/c	
Bottom Edge (Lu)	20' 5" o/c	

- Maximum allowable bracing intervals based on applied load.

Connector: Simpson Strong-Tie

Support	Model	Seat Length	Top Fasteners	Face Fasteners	Member Fasteners	Accessories
3 - Top Mount Hanger	THA422	1.75"	4-16d	2-16d	6-10d	

- Refer to manufacturer notes and instructions for proper installation and use of all connectors.

Vertical Loads	Location (Side)	Tributary Width	Dead (0.90)	Roof Live (1.25)	Snow (1.15)	Comments
0 - Self Weight (PLF)	0 to 20' 5"	N/A	10.1	--	--	
1 - Uniform (PSF)	0 to 20' 10 1/2" (Front)	2'	15.0	20.0	42.0	Default Load
2 - Point (lb)	0 (Front)	N/A	718	781	1639	Linked from: Roof Beam RB3, Support 1

- Side loads are assumed to not induce cross-grain tension.

ForteWEB Software Operator	Job Notes
Asrade Mengstu Cushing Terrell (406) 500-3544 asrademengstu@cushingterrell.com	

Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to www.weyerhaeuser.com/woodproducts/document-library.


The product application, input design loads, dimensions and support information have been provided by ForteWEB Software Operator

ForteWEB Software Operator	Job Notes
Asrade Mengstu Cushing Terrell (406) 500-3544 asrademengstu@cushingterrell.com	



Roof, Roof Beam RB5

1 piece(s) 3 1/2" x 11 7/8" 24F-V8 DF Glulam



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	992 @ 19' 11 1/2"	3413 (1.50")	Passed (29%)	--	1.0 D + 1.0 S (Alt Spans)
Shear (lbs)	1334 @ 1' 1/8"	8444	Passed (16%)	1.15	1.0 D + 1.0 S (All Spans)
Pos Moment (Ft-lbs)	3963 @ 11' 11 5/8"	18920	Passed (21%)	1.15	1.0 D + 1.0 S (Alt Spans)
Neg Moment (Ft-lbs)	-3003 @ 2' 2 3/4"	18920	Passed (16%)	1.15	1.0 D + 1.0 S (All Spans)
Live Load Defl. (in)	0.171 @ 11' 4 9/16"	0.886	Passed (L/999+)	--	1.0 D + 1.0 S (Alt Spans)
Total Load Defl. (in)	0.240 @ 11' 5 7/16"	1.182	Passed (L/886)	--	1.0 D + 1.0 S (Alt Spans)

Member Length : 19' 11 1/2"

System : Roof

Member Type : Drop Beam

Building Use : Residential

Building Code : IBC 2021

Design Methodology : ASD

Member Pitch : 0/12

- Deflection criteria: LL (L/240) and TL (L/180).
- Overhang deflection criteria: LL (2L/240) and TL (2L/180).
- Allowed moment does not reflect the adjustment for the beam stability factor.
- Volume factor of 1.00 was calculated for positive bending using length L = 15' 11 13/16".
- Volume factor of 1.00 was calculated for negative bending using length L = 4' 11 1/2".
- The effects of positive or negative camber have not been accounted for when calculating deflection.
- Applicable calculations are based on NDS.

Supports	Bearing Length			Loads to Supports (lbs)				Accessories
	Total	Available	Required	Dead	Roof Live	Snow	Factored	
1 - Beam - DF	5.50"	5.50"	1.50"	823	920	1932	2755	None
2 - Hanger on 11 7/8" GLB beam	5.50"	Hanger ¹	1.50"	322	344	722	1044	See note ¹

At hanger supports, the Total Bearing dimension is equal to the width of the material that is supporting the hanger

¹ See Connector grid below for additional information and/or requirements.

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	20' o/c	
Bottom Edge (Lu)	20' o/c	

Maximum allowable bracing intervals based on applied load.

Connector: Simpson Strong-Tie

Support	Model	Seat Length	Top Fasteners	Face Fasteners	Member Fasteners	Accessories
2 - Top Mount Hanger	THA422	1.75"	4-16d	2-16d	6-10d	

Refer to manufacturer notes and instructions for proper installation and use of all connectors.

Vertical Loads	Location (Side)	Tributary Width	Dead (0.90)	Roof Live (1.25)	Snow (1.15)	Comments
0 - Self Weight (PLF)	0 to 19' 11 1/2"	N/A	10.1	--	--	
1 - Uniform (PSF)	0 to 20' 5" (Front)	2'	15.0	20.0	42.0	Default Load
2 - Point (lb)	0 (Front)	N/A	331	418	878	Linked from: Roof Beam RB3, Support 2

Side loads are assumed to not induce cross-grain tension.

ForteWEB Software Operator	Job Notes
Asrade Mengstu Cushing Terrell (406) 500-3544 asrademengstu@cushingterrell.com	

Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to www.weyerhaeuser.com/woodproducts/document-library.


The product application, input design loads, dimensions and support information have been provided by ForteWEB Software Operator

ForteWEB Software Operator	Job Notes
Asrade Mengstu Cushing Terrell (406) 500-3544 asrademengstu@cushingterrell.com	



Roof, Roof Header Beam RH1

1 piece(s) 3 1/2" x 10 1/2" 24F-V4 DF Glulam



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	4329 @ 1 1/2"	6825 (3.00")	Passed (63%)	--	1.0 D + 1.0 S (All Spans)
Shear (lbs)	3517 @ 1' 1 1/2"	7466	Passed (47%)	1.15	1.0 D + 1.0 S (All Spans)
Pos Moment (Ft-lbs)	12450 @ 6'	14792	Passed (84%)	1.15	1.0 D + 1.0 S (All Spans)
Live Load Defl. (in)	0.370 @ 6'	0.587	Passed (L/381)	--	1.0 D + 1.0 S (All Spans)
Total Load Defl. (in)	0.509 @ 6'	0.783	Passed (L/277)	--	1.0 D + 1.0 S (All Spans)

Member Length : 12'
 System : Roof
 Member Type : Drop Beam
 Building Use : Residential
 Building Code : IBC 2021
 Design Methodology : ASD
 Member Pitch : 0/12

- Deflection criteria: LL (L/240) and TL (L/180).
- Allowed moment does not reflect the adjustment for the beam stability factor.
- Volume factor of 1.00 was calculated for positive bending using length L = 11' 9".
- The effects of positive or negative camber have not been accounted for when calculating deflection.
- The specified glulam is assumed to have its strong laminations at the bottom of the beam. Install with proper side up as indicated by the manufacturer.
- Applicable calculations are based on NDS.

Supports	Bearing Length			Loads to Supports (lbs)				Accessories
	Total	Available	Required	Dead	Roof Live	Snow	Factored	
1 - Trimmer - DF	3.00"	3.00"	1.90"	1179	1500	3150	4329	None
2 - Trimmer - DF	3.00"	3.00"	1.90"	1179	1500	3150	4329	None

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	12' o/c	
Bottom Edge (Lu)	12' o/c	

• Maximum allowable bracing intervals based on applied load.

Vertical Loads	Location (Side)	Tributary Width	Dead (0.90)	Roof Live (1.25)	Snow (1.15)	Comments
0 - Self Weight (PLF)	0 to 12'	N/A	8.9	--	--	
1 - Uniform (PSF)	0 to 12' (Front)	12' 6"	15.0	20.0	42.0	Default Load

• Side loads are assumed to not induce cross-grain tension.

Weyerhaeuser Notes


Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to www.weyerhaeuser.com/woodproducts/document-library.

The product application, input design loads, dimensions and support information have been provided by ForteWEB Software Operator

ForteWEB Software Operator	Job Notes
Asrade Mengstu Cushing Terrell (406) 500-3544 asrademengstu@cushingterrell.com	

Roof, Roof Header Beam RH2

1 piece(s) 4 x 6 DF No.2



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	1948 @ 1 1/2"	6563 (3.00")	Passed (30%)	--	1.0 D + 1.0 S (All Spans)
Shear (lbs)	1258 @ 8 1/2"	2657	Passed (47%)	1.15	1.0 D + 1.0 S (All Spans)
Moment (Ft-lbs)	1712 @ 2'	1979	Passed (87%)	1.15	1.0 D + 1.0 S (All Spans)
Live Load Defl. (in)	0.041 @ 2'	0.188	Passed (L/999+)	--	1.0 D + 1.0 S (All Spans)
Total Load Defl. (in)	0.056 @ 2'	0.250	Passed (L/806)	--	1.0 D + 1.0 S (All Spans)

- Deflection criteria: LL (L/240) and TL (L/180).
- Allowed moment does not reflect the adjustment for the beam stability factor.
- Applicable calculations are based on NDS.

Member Length : 4'
System : Roof
Member Type : Drop Beam
Building Use : Residential
Building Code : IBC 2021
Design Methodology : ASD
Member Pitch : 0/12

Supports	Bearing Length			Loads to Supports (lbs)				Accessories
	Total	Available	Required	Dead	Roof Live	Snow	Factored	
1 - Trimmer - DF	3.00"	3.00"	1.50"	520	680	1428	1948	None
2 - Trimmer - DF	3.00"	3.00"	1.50"	520	680	1428	1948	None

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	4' o/c	
Bottom Edge (Lu)	4' o/c	

- Maximum allowable bracing intervals based on applied load.

Vertical Loads	Location (Side)	Tributary Width	Dead (0.90)	Roof Live (1.25)	Snow (1.15)	Comments
0 - Self Weight (PLF)	0 to 4'	N/A	4.9	--	--	
1 - Uniform (PSF)	0 to 4' (Front)	17'	15.0	20.0	42.0	Default Load

- Side loads are assumed to not induce cross-grain tension.

Weyerhaeuser Notes


Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to www.weyerhaeuser.com/woodproducts/document-library.

The product application, input design loads, dimensions and support information have been provided by ForteWEB Software Operator

ForteWEB Software Operator	Job Notes
Asrade Mengstu Cushing Terrell (406) 500-3544 asrademengstu@cushingterrell.com	

Roof, Roof Header Beam RH3

1 piece(s) 4 x 10 DF No.2



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	1298 @ 1' 1/2"	6563 (3.00")	Passed (20%)	--	1.0 D + 1.0 S (All Spans)
Shear (lbs)	1086 @ 1' 1/4"	4468	Passed (24%)	1.15	1.0 D + 1.0 S (All Spans)
Moment (Ft-lbs)	3896 @ 6' 3"	5166	Passed (75%)	1.15	1.0 D + 1.0 S (All Spans)
Live Load Defl. (in)	0.202 @ 6' 3"	0.613	Passed (L/729)	--	1.0 D + 1.0 S (All Spans)
Total Load Defl. (in)	0.285 @ 6' 3"	0.817	Passed (L/516)	--	1.0 D + 1.0 S (All Spans)

- Deflection criteria: LL (L/240) and TL (L/180).
- Allowed moment does not reflect the adjustment for the beam stability factor.
- Applicable calculations are based on NDS.

Member Length : 12' 6"
System : Roof
Member Type : Drop Beam
Building Use : Residential
Building Code : IBC 2021
Design Methodology : ASD
Member Pitch : 0/12

Supports	Bearing Length			Loads to Supports (lbs)				Accessories
	Total	Available	Required	Dead	Roof Live	Snow	Factored	
1 - Trimmer - DF	3.00"	3.00"	1.50"	379	438	919	1298	None
2 - Trimmer - DF	3.00"	3.00"	1.50"	379	438	919	1298	None

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	12' 6" o/c	
Bottom Edge (Lu)	12' 6" o/c	

- Maximum allowable bracing intervals based on applied load.

Vertical Loads	Location (Side)	Tributary Width	Dead (0.90)	Roof Live (1.25)	Snow (1.15)	Comments
0 - Self Weight (PLF)	0 to 12' 6"	N/A	8.2	--	--	
1 - Uniform (PSF)	0 to 12' 6" (Front)	3' 6"	15.0	20.0	42.0	Default Load

- Side loads are assumed to not induce cross-grain tension.

Weyerhaeuser Notes


Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to www.weyerhaeuser.com/woodproducts/document-library.

The product application, input design loads, dimensions and support information have been provided by ForteWEB Software Operator

ForteWEB Software Operator	Job Notes
Asrade Mengstu Cushing Terrell (406) 500-3544 asrademengstu@cushingterrell.com	

Roof, Roof Header Beam RH4

1 piece(s) 4 x 10 DF No.2



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	987 @ 1' 1/2"	6563 (3.00")	Passed (15%)	--	1.0 D + 1.0 S (All Spans)
Shear (lbs)	775 @ 1' 1/4"	4468	Passed (17%)	1.15	1.0 D + 1.0 S (All Spans)
Moment (Ft-lbs)	2221 @ 4' 9"	5166	Passed (43%)	1.15	1.0 D + 1.0 S (All Spans)
Live Load Defl. (in)	0.066 @ 4' 9"	0.463	Passed (L/999+)	--	1.0 D + 1.0 S (All Spans)
Total Load Defl. (in)	0.093 @ 4' 9"	0.617	Passed (L/999+)	--	1.0 D + 1.0 S (All Spans)

- Deflection criteria: LL (L/240) and TL (L/180).
- Allowed moment does not reflect the adjustment for the beam stability factor.
- Applicable calculations are based on NDS.

Member Length : 9' 6"
System : Roof
Member Type : Drop Beam
Building Use : Residential
Building Code : IBC 2021
Design Methodology : ASD
Member Pitch : 0/12

Supports	Bearing Length			Loads to Supports (lbs)				Accessories
	Total	Available	Required	Dead	Roof Live	Snow	Factored	
1 - Trimmer - DF	3.00"	3.00"	1.50"	288	333	698	987	None
2 - Trimmer - DF	3.00"	3.00"	1.50"	288	333	698	987	None

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	9' 6" o/c	
Bottom Edge (Lu)	9' 6" o/c	

- Maximum allowable bracing intervals based on applied load.

Vertical Loads	Location (Side)	Tributary Width	Dead (0.90)	Roof Live (1.25)	Snow (1.15)	Comments
0 - Self Weight (PLF)	0 to 9' 6"	N/A	8.2	--	--	
1 - Uniform (PSF)	0 to 9' 6" (Front)	3' 6"	15.0	20.0	42.0	Default Load

- Side loads are assumed to not induce cross-grain tension.

Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to www.weyerhaeuser.com/woodproducts/document-library.

The product application, input design loads, dimensions and support information have been provided by ForteWEB Software Operator

ForteWEB Software Operator	Job Notes
Asrade Mengstu Cushing Terrell (406) 500-3544 asrademengstu@cushingterrell.com	

SEARCHC WRANGELL - STAFF HOUSING - 1064 ZIMOVIA HWY
WRANGELL AK 99929

SINGLE BEDROOM DUPLEX (SHED ROOF)

LATERAL ANALYSIS

WIND ANALYSIS

$$V = 139 \text{ mph}, \text{ Exp 'D', } K_{zt} = 1.0$$

SEE ATTACHED WIND PRESSURE CALCULATIONS (STRUWARE)

→ WIND IN N-S DIRECTION:

$$\text{ROOF} = 427 \text{ s.f.} \times 29 \text{ psf} = 12,383 \#$$

→ WIND IN E-W DIRECTION:

$$\text{ROOF} = 268 \times 29 = 7,772 \#$$

SEISMIC ANALYSIS

SEISMIC DEAD LOAD:

$$\begin{aligned} \text{ROOF DL} &= 2,334 \times 18 + 2(56 + 35) \times 11/2 \times 15 \text{ psf} \\ &= 42,012 + 15,015 = 57,027 \# \end{aligned}$$

FROM ATTACHED CALCULATIONS, $V = 0.021$ $W = 1.2k$ (ASD)

⇒ WIND GOVERNS BOTH DIRECTIONS.

ASCE Hazards Report

Address:
No Address at This Location

Standard: ASCE/SEI 7-16
Risk Category: II
Soil Class: B - Rock

Latitude: 56.460443
Longitude: -132.376976
Elevation: 96.81758915131236 ft (NAVD 88)



Wind

Results:

Wind Speed	139 Vmph
10-year MRI	98 Vmph
25-year MRI	106 Vmph
50-year MRI	113 Vmph
100-year MRI	119 Vmph

Data Source: ASCE/SEI 7-16, Fig. 26.5-1B and Figs. CC.2-1–CC.2-4, and Section 26.5.2
Date Accessed: Mon Aug 18 2025





Value provided is 3-second gust wind speeds at 33 ft above ground for Exposure C Category, based on linear interpolation between contours. Wind speeds are interpolated in accordance with the 7-16 Standard. Wind speeds correspond to approximately a 7% probability of exceedance in 50 years (annual exceedance probability = 0.00143, MRI = 700 years).

Site is not in a hurricane-prone region as defined in ASCE/SEI 7-16 Section 26.2.

Site Soil Class: B - Rock

Results:

S_S :	0.249	S_{D1} :	0.136
S_1 :	0.254	T_L :	12
F_a :	0.9	PGA :	0.093
F_v :	0.8	PGA _M :	0.083
S_{MS} :	0.224	F_{PGA} :	0.9
S_{M1} :	0.204	I_e :	1
S_{DS} :	0.149	C_v :	0.749



Data Accessed: Mon Aug 18 2025

Date Source:

USGS Seismic Design Maps based on ASCE/SEI 7-16 and ASCE/SEI 7-16 Table 1.5-2. Additional data for site-specific ground motion procedures in accordance with ASCE/SEI 7-16 Ch. 21 are available from USGS.

Results:

Ground Snow Load, p_g :	60 lb/ft ²
Mapped Elevation:	96.8 ft
Data Source:	ASCE/SEI 7-16, Table 7.2-8
Date Accessed:	Mon Aug 18 2025

Values provided are ground snow loads. In areas designated "case study required," extreme local variations in ground snow loads preclude mapping at this scale. Site-specific case studies are required to establish ground snow loads at elevations not covered.

Snow load values are mapped to a 0.5 mile resolution. This resolution can create a mismatch between the mapped elevation and the site-specific elevation in topographically complex areas. Engineers should consult the local authority having jurisdiction in locations where the reported 'elevation' and 'mapped elevation' differ significantly from each other.

The ASCE Hazard Tool is provided for your convenience, for informational purposes only, and is provided "as is" and without warranties of any kind. The location data included herein has been obtained from information developed, produced, and maintained by third party providers; or has been extrapolated from maps incorporated in the ASCE standard. While ASCE has made every effort to use data obtained from reliable sources or methodologies, ASCE does not make any representations or warranties as to the accuracy, completeness, reliability, currency, or quality of any data provided herein. Any third-party links provided by this Tool should not be construed as an endorsement, affiliation, relationship, or sponsorship of such third-party content by or from ASCE.

ASCE does not intend, nor should anyone interpret, the results provided by this Tool to replace the sound judgment of a competent professional, having knowledge and experience in the appropriate field(s) of practice, nor to substitute for the standard of care required of such professionals in interpreting and applying the contents of this Tool or the ASCE standard.

In using this Tool, you expressly assume all risks associated with your use. Under no circumstances shall ASCE or its officers, directors, employees, members, affiliates, or agents be liable to you or any other person for any direct, indirect, special, incidental, or consequential damages arising from or related to your use of, or reliance on, the Tool or any information obtained therein. To the fullest extent permitted by law, you agree to release and hold harmless ASCE from any and all liability of any nature arising out of or resulting from any use of data provided by the ASCE Hazard Tool.

SEISMIC BASE SHEAR: ASCE 7-16

Occupancy Category = 1
 Site Class = B
 Lat. = 56.460
 Long. = -132.377
 Ss = 24.9 % g
 S1 = 25.4 % g

Seismic Design
 Category (SDC) = C
 Fa = 0.900
 Fv = 0.8
 Sds = 0.149
 Sd1 = 0.135

Vmin = 0.044*Sds W : 0.01
 V = Sds*I W : 0.02
 R = 6.5
 Vmax = Sd1*I W : 0.17
 R*T

Where: Sds = 0.149
 Sd1 = 0.135
 I = 1
 R = 6.5
 T expo' = 0.75
 Ct = 0.02
 Hn = 11
 T = 0.121
 Total W = 57.0 kips

Therefore: V.ult = 0.023 W V = 1.3 kips
 V.service = 0.016 W V = 0.9 kips

E = ρ Eh + Ev
 where ρ = 1.0 or 1.3
 ρ.y = 1.3
 ρ.x = 1.3

INCREASE SEISMIC

V.ult = 0.030 W V = 1.7 kips
 V.service = 0.021 W V = 1.2 kips

Note: IBC Ax and r are evaluated at each floor

Therefore: pEx = 1.7 kips pEy = 1.7 kips
 pEx = 1.2 kips pEy = 1.2 kips
 static distribution is relative to T = 0.121 sec linear
 building period distribution ----> k (exponent) = 1.00

SEISMIC DISTRIBUTION: X-Direction

level	W (kips)	h (ft)	Wh ^k (kip-ft)	STRENGTH / LRFD		ALLOW. STRESS DESIGN		Diaphragm	
				Wh ^k Σ Wh ^k	story shear (kips)	Σ (kips)	story shear (kips)	Σ (kips)	Scaled Seismic (kips)
Roof	57.0	11	627	1.00	1.7	1.7	1.2	1.2	0.016
Σ	57.0		627	1	1.7		1.2		0.016
							.7E	.7E	.7E

SEISMIC DISTRIBUTION: Y-Direction

level	W (kips)	h (ft)	Wh ^k (kip-ft)	STRENGTH / LRFD		ALLOW. STRESS DESIGN		Diaphragm	
				Wh ^k Σ Wh ^k	story shear (kips)	Σ (kips)	story shear (kips)	Σ (kips)	Scaled Seismic (kips)
Roof	57.0	10	570	1.00	1.7	1.7	1.2	1.2	0.016
Σ	57.0		570	1	1.7		1.2		0.016
							.7E	.7E	.7E

SEARHC WRANGELL - 1bdDupShed

Fa	Ss				
	Ss <	Ss =	Ss =	Ss =	Ss >
A	0.25	0.5	0.75	1	1.25
B	0.8	0.8	0.8	0.8	0.8
C	1	1	1	1	1
D	1.2	1.2	1.1	1	1
E	1.6	1.4	1.2	1.1	1
F	2.5	1.7	1.2	0.9	0.9
F	a	a	a	a	a
Fv	S1				
	S1 <	S1 =	S1 =	S1 =	S1 >
A	0.1	0.2	0.3	0.4	0.5
B	0.8	0.8	0.8	0.8	0.8
C	1	1	1	1	1
D	1.7	1.6	1.5	1.4	1.3
E	2.4	2	1.8	1.6	1.5
F	3.5	3.2	2.8	2.4	2.4
F	a	a	a	a	a

T exponer	Ct
0.75	0.02 default
0.75	0.03 Ecc Braced Frames
0.8	0.016 Concrete Moment Frames
0.9	0.028 Steel Moment Frames

Common Values		
	R	omega
Wood SW	6.5	3 bearing wall system
Special Conc SW	5	2.5 bearing wall system
Special CMU SW	5	2.5 bearing wall system
Steel OMRF	3.5	3 building frame system
Steel SMRF	8	3 building frame system
Steel OBF	5	2 building frame system
Steel SBF	6	2 building frame system
Cant Col		building frame system

STRUCTURAL CALCULATIONS

FOR

SEARHC Wrangell - Staff Housing

Wrangell, Alaska

Code Search

Code: International Building Code 2021

Occupancy:

Occupancy Group = R Residential

Risk Category & Importance Factors:

Risk Category = II

Wind factor = 1.00 use 0.60 NOTE: Output will be nominal wind pressures

Snow factor = 1.00

Seismic factor = 1.00

Type of Construction:

Fire Rating:

Roof = 1.0 hr

Floor = 1.0 hr

Building Geometry:

Roof angle (θ) 0.75 / 12 3.6 deg

Building length 57.0 ft

Least width 35.0 ft

Mean Roof Ht (h) 12.0 ft

Parapet ht above grd 0.0 ft

Minimum parapet ht 0.0 ft

Live Loads:

Roof 0 to 200 sf: 20 psf

200 to 600 sf: 24 - 0.02Area, but not less than 12 psf

over 600 sf: 12 psf

Floor:

Typical Floor 40 psf

Partitions N/A

0 psf

0 0 psf

Stairs and exit ways 100 psf

Wind Loads :

ASCE 7- 16

Ultimate Wind Speed	139 mph
Nominal Wind Speed	107.7 mph
Risk Category	II
Exposure Category	D
Enclosure Classif.	Enclosed Building
Internal pressure	+/-0.18
Directionality (Kd)	0.85
Kh case 1	1.030
Kh case 2	1.030
Type of roof	Monoslope

Topographic Factor (Kzt)

Topography	2D Escarpment
Hill Height (H)	20.0 ft
Half Hill Length (Lh)	300.0 ft
Actual H/Lh	= 0.07
Use H/Lh	= 0.00
Modified Lh	= 300.0 ft
From top of crest: x =	50.0 ft
Bldg up/down wind?	downwind

$$H/Lh = 0.00 \quad K_1 = 0.000$$


$$x/Lh = 0.17 \quad K_2 = 0.958$$

$$z/Lh = 0.05 \quad K_3 = 0.882$$


At Mean Roof Ht:

$$K_{zt} = (1 + K_1 K_2 K_3)^2 = 1.00$$

$$H/Lh < 0.2 \\ \therefore K_{zt} = 1.0$$



ESCARPMENT



2D RIDGE or 3D AXISYMMETRICAL HILL

Gust Effect Factor

h =	12.0 ft
B =	35.0 ft
/z (0.6h) =	7.2 ft

Flexible structure if natural frequency < 1 Hz (T > 1 second).

If building h/B > 4 then may be flexible and should be investigated.

$$h/B = 0.34 \quad \text{Rigid structure (low rise bldg)}$$

$$G = 0.85 \quad \text{Using rigid structure default}$$

Rigid Structure

\bar{e} =	0.13
ℓ =	650 ft
z_{min} =	7 ft
c =	0.15
g_Q, g_v =	3.4
L_z =	537.4 ft
Q =	0.94
I_z =	0.19
G =	0.89 use G = 0.85

Flexible or Dynamically Sensitive Structure

Natural Frequency (η_1) =	0.0 Hz		
Damping ratio (β) =	0		
$/b$ =	0.80		
$/\alpha$ =	0.11		
V_z =	137.7		
N_1 =	0.00		
R_n =	0.000		
R_h =	28.282	$\eta =$	0.000
R_B =	28.282	$\eta =$	0.000
R_L =	28.282	$\eta =$	0.000
g_R =	0.000		
R =	0.000		
Gf =	0.000		

$$h = 12.0 \text{ ft}$$

Enclosure Classification

Test for Enclosed Building: $A_o < 0.01A_g$ or 4 sf, whichever is smaller

Test for Open Building: All walls are at least 80% open.
 $A_o \geq 0.8A_g$

Test for Partially Enclosed Building: Predominately open on one side only

Input		Test	
Ao	500.0 sf	$A_o \geq 1.1A_{oi}$	NO
Ag	600.0 sf	$A_o > 4'$ or $0.01A_g$	YES
Aoi	1000.0 sf	$A_{oi} / A_{gi} \leq 0.20$	YES
Agi	10000.0 sf		

Building is NOT
Partially Enclosed

Conditions to qualify as Partially Enclosed Building. Must satisfy all of the following:

$A_o \geq 1.1A_{oi}$

$A_o >$ smaller of 4' or 0.01 Ag

$A_{oi} / A_{gi} \leq 0.20$

Where:

A_o = the total area of openings in a wall that receives positive external pressure.

A_g = the gross area of that wall in which A_o is identified.

A_{oi} = the sum of the areas of openings in the building envelope (walls and roof) not including A_o .

A_{gi} = the sum of the gross surface areas of the building envelope (walls and roof) not including A_g .

Test for Partially Open Building: A building that does not qualify as open, enclosed or partially enclosed.
(This type building will have same wind pressures as an enclosed building.)

Reduction Factor for large volume partially enclosed buildings (Ri) :

If the partially enclosed building contains a single room that is unpartitioned , the internal pressure coefficient may be multiplied by the reduction factor Ri.

Total area of all wall & roof openings (A_{og}): 0 sf

Unpartitioned internal volume (V_i) : 0 cf

Ri = 1.00

Ground Elevation Factor (Ke)

Grd level above sea level = 0.0 ft

Constant = 0.00256

Adj Constant = 0.00256

Ke = 1.0000

Wind Loads - MWFRS all h (Except for Open Buildings)

Kh (case 2) =	1.03			GCpi =	+/-0.18
Base pressure (qh) =	26.0 psf	Bldg dim parallel to ridge =	57.0 ft	G =	0.85
Roof Angle (θ) =	3.6 deg	Bldg dim normal to ridge =	35.0 ft	qi = qh	
Roof tributary area:		h =	12.0 ft		
Wind normal to ridge =(h/2)*L:	342 sf	ridge ht =	13.1 ft		
Wind parallel to ridge =(h/2)*L:	210 sf				

Nominal Wind Surface Pressures (psf)

Surface	Wind Normal to Ridge				Wind Parallel to Ridge				
	L/B = 0.61		h/L = 0.34		L/B = 1.63		h/L = 0.21		
	Cp	qhGCp	w/+q _i GC _{pi}	w/-q _i GC _{pi}	Dist.*	Cp	qhGCp	w/ +q _i GC _{pi}	w/ -q _i GC _{pi}
Windward Wall (WW)	0.80	17.7	see table below			0.80	17.7	see table below	
Leeward Wall (LW)	-0.50	-11.0	-15.7	-6.4		-0.37	-8.3	-12.9	-3.6
Side Wall (SW)	-0.70	-15.5	-20.1	-10.8		-0.70	-15.5	-20.1	-10.8
Leeward Roof (LR)	**					Included in windward roof			
Neg Windward Roof: 0 to h/2*	-0.90	-19.9	-24.6	-15.2	0 to h/2*	-0.90	-19.9	-24.6	-15.2
h/2 to h*	-0.90	-19.9	-24.6	-15.2	h/2 to h*	-0.90	-19.9	-24.6	-15.2
h to 2h*	-0.50	-11.0	-15.7	-6.4	h to 2h*	-0.50	-11.0	-15.7	-6.4
> 2h*	-0.30	-6.6	-11.3	-1.9	> 2h*	-0.30	-6.6	-11.3	-1.9
Pos/min windward roof press.	-0.18	-4.0	-8.7	0.7	Min press.	-0.18	-4.0	-8.7	0.7

**Roof angle < 10 degrees. Therefore, leeward roof is included in windward roof pressure zones.

*Horizontal distance from windward edge

For monoslope roofs, entire roof surface is either windward or leeward surface.

Parapet

z	Kz	Kzt	qp (psf)
0.0 ft	1.03	1.00	0.0


Windward parapet: 0.0 psf (GCpn = +1.5)

Leeward parapet: 0.0 psf (GCpn = -1.0)


Windward roof overhangs : 17.7 psf (upward - add to windward roof pressure)

Windward Wall Pressures at "z" (psf)


z	Kz	Kzt	Windward Wall			Combined WW + LW	
			qzGCp	w/+qiGCpi	w/-qhGCpi	Wind Normal to Ridge	Wind Parallel to Ridge
h= 0 to 15'	1.03	1.00	17.7	13.0	22.3	28.7	25.9



WIND NORMAL TO RIDGE




WIND PARALLEL TO RIDGE



TYPICAL WIND LOADING

NOTE: ASCE 7 requires the application of full and partial loading of the wind pressures per the 4 cases below.



Wind Forces at Floors

Total Floors = 1
 T/Fdn (dist below grade) = 2.0 ft

Building dimension (parallel with ridge) = 57.0 ft
 Building dimension (normal to ridge) = 35.0 ft
 L is the building dimension parallel to the wind direction

e = 8.55 ft
 e = 5.25 ft

Level	Elevation Above Grade (ft)	Height of Centroid to Fdn (ft)	Wind Normal to Ridge						Wind Parallel to Ridge			
			L	B	Area (sf)	Applied Force (k)	Story Shear (k)	Overturning Moment (k)	Area	Applied Force (k)	Story Shear (k)	Overturning Moment (k)
Equip, etc		0.00	wind on equip, screenwalls, etc =									0.0
Parapet	0.00	0.00				0.0		0.0		0.0		0.0
T/Ridge	0.00	0.00			0.0	0.0		0.0	0.0	0.0		0.0
Roof	15.00	17.00	35.0	57.0	427.5	12.3	12.3	0.0	262.5	6.8	6.8	0.0
1	0.00	2.00	35.0	57.0	427.5	12.3	24.6	184.1	262.5	6.8	13.6	102.1
Fdn		0.00						233.3				129.4

Nominal Wind Pressures

Wind Loads - Components & Cladding : $h \leq 60'$

Kh (case 2) = 1.03 h = 12.0 ft
Base pressure (qh) = **26.0 psf** a = 3.5 ft
Minimum parapet ht = 0.0 ft GCpi = +/-0.18
Roof Angle (θ) = 3.6 deg qi = qh = 26.0 psf
Type of roof = Monoslope

Roof

Area	GCp +/- GCpi				Surface Pressure (psf)			
	10 sf	20 sf	50 sf	100 sf	10 sf	20 sf	50 sf	100 sf
Negative Zone 1	-1.28	-1.28	-1.28	-1.28	-33.3	-33.3	-33.3	-33.3
Negative Zone 2	-1.48	-1.45	-1.41	-1.38	-38.5	-37.7	-36.6	-35.9
Negative Zone 2'	-1.78	-1.75	-1.71	-1.68	-46.3	-45.5	-44.4	-43.7
Negative Zone 3	-1.98	-1.8	-1.56	-1.38	-51.5	-46.8	-40.6	-35.9
Negative Zone 3'	-2.78	-2.48	-2.08	-1.78	-72.2	-64.4	-54.1	-46.3
Positive All Zones	0.48	0.45	0.41	0.38	12.5	11.7	10.7	10.0

User input	
75 sf	150 sf
-33.3	-33.3
-36.2	-35.9
-44.0	-43.7
-37.8	-35.9
-49.5	-46.3
10.2	10.0

Parapet

qp = 0.0 psf

		Surface Pressure (psf)					
		10 sf	20 sf	50 sf	100 sf	200 sf	500 sf
Solid Parapet Pressure							
CASE A:	Zone 2 :	0.0	0.0	0.0	0.0	0.0	0.0
	Zone 2' :	0.0	0.0	0.0	0.0	0.0	0.0
	Zone 3 :	0.0	0.0	0.0	0.0	0.0	0.0
	Zone 3' :	0.0	0.0	0.0	0.0	0.0	0.0
CASE B:							
Interior zone :		0.0	0.0	0.0	0.0	0.0	0.0
Corner zone :		0.0	0.0	0.0	0.0	0.0	0.0

User input	
40 sf	
0.0	
0.0	
0.0	
0.0	
0.0	
0.0	


Walls

Area	GCp +/- GCpi				Surface Pressure at h			
	10 sf	100 sf	200 sf	500 sf	10 sf	100 sf	200 sf	500 sf
Negative Zone 4	-1.17	-1.01	-0.96	-0.90	-30.4	-26.3	-25.0	-23.4
Negative Zone 5	-1.44	-1.12	-1.03	-0.90	-37.4	-29.2	-26.7	-23.4
Positive Zone 4 & 5	1.08	0.92	0.87	0.81	28.1	23.9	22.7	21.1


User input	
50 sf	300 sf
-27.5	-24.3
-31.6	-25.2
25.2	22.0

Note: GCp reduced by 10% due to roof angle ≤ 10 deg.


Location of C&C Wind Pressure Zones - ASCE 7-16




Roofs w/ $\theta \leq 10^\circ$
and all walls
 $h > 60'$




Walls $h \leq 60'$
& alt design $h < 90'$




Gable, Sawtooth and
Multispan Gable $\theta \leq 7$ degrees &
Monoslope ≤ 3 degrees
 $h \leq 60'$ & alt design $h < 90'$




Monoslope roofs
 $3^\circ < \theta \leq 10^\circ$
 $h \leq 60'$ & alt design $h < 90'$





Monoslope roofs
 $10^\circ < \theta \leq 30^\circ$
 $h \leq 60'$ & alt design $h < 90'$




Multispan Gable &
Gable $7^\circ < \theta \leq 45^\circ$




Hip $7^\circ < \theta \leq 27^\circ$



Sawtooth $10^\circ < \theta \leq 45^\circ$
 $h \leq 60'$ & alt design $h < 90'$




Stepped roofs $\theta \leq 3^\circ$
 $h \leq 60'$ & alt design $h < 90'$




Note: The stepped roof zones above are as shown in ASCE 7-16 (except the upper roof zones 1 and 2 are shown at the inside edge per the notes). Prior editions didn't show zones, but the notes sent you to the low slope gable figure. The note in ASCE 7-16 still sends you to the low slope gable figure, but for some reasons the zones shown are per editions prior to ASCE 7-16. Therefore, the above zones may be a code mistake and the correct zone locations may be per the low slope gable roof shown at the top of this page.


Location of C&C Wind Pressure Zones - ASCE 7-10 & earlier




Roofs w/ $\theta \leq 10^\circ$
and all walls
 $h > 60'$




Walls $h \leq 60'$
& alt design $h < 90'$




Gable, Sawtooth and
Multispan Gable $\theta \leq 7$ degrees &
Monoslope ≤ 3 degrees
 $h \leq 60'$ & alt design $h < 90'$




Monoslope roofs
 $3^\circ < \theta \leq 10^\circ$
 $h \leq 60'$ & alt design $h < 90'$





Monoslope roofs
 $10^\circ < \theta \leq 30^\circ$
 $h \leq 60'$ & alt design $h < 90'$




Multispan Gable &
Gable $7^\circ < \theta \leq 45^\circ$




Hip $7^\circ < \theta \leq 27^\circ$



Sawtooth $10^\circ < \theta \leq 45^\circ$
 $h \leq 60'$ & alt design $h < 90'$



Stepped roofs $\theta \leq 3^\circ$
 $h \leq 60'$ & alt design $h < 90'$



SEARHC WRANGELL - 1bdDupShed

V in N-S Roof
shear (k) = 12.40 (Wind)

Wall	TW (ft)	V (k)	L (ft)	v (plf)	SW Type	h (ft)	Mot (k-ft)	TW (ft)	DLroof (psf)	Wfl (plf)	DLwall (psf)	Wwall (plf)	Mr (k-ft)	.6Mr (k-ft)	FS	T (lbs)	Holdowns	Wall
1	12.5	2.77	8	346	SWB													1
3	15.5	3.43	19.5	176	SWA													3
4	15.5	3.43	19.5	176	SWA													4
6	12.5	2.77	8	346	SWB													6
56																		

* Shearwall capacity reduced by 1.25-0.125h/b

Holdowns

V in N-S	Roof																	
Wall	L (ft)	h (ft)	Mot (k-ft)	TW (ft)	DLroof (psf)	Wfl (plf)	DLwall (psf)	Wwall (plf)	Mr (k-ft)	.6Mr (k-ft)	FS	T (lbs)	Holdowns	Wall	C (lbs)			
v=	346	plf																
1	8	11	30.45	2	18	36	10	110	5	2.8	0.09	3455	4	1	3806			
v=	176	plf																
3a	12.5	11	24.20	6	18	108	10	110	17	10.2	0.42	1119	4	3a	1936			
3b	7	11	13.55	6	18	108	10	110	5	3.2	0.24	1478	4	3b	1936			
v=	176	plf																
4a	12.5	11	24.20	6	18	108	10	110	17	10.2	0.42	1119	4	4a	1936			
4b	7	11	13.55	6	18	108	10	110	5	3.2	0.24	1478	4	4b	1936			
v=	346	plf																
6	8	11	30.45	2	18	36	10	110	5	2.8	0.09	3455	4	6	3806			

SEARHC WRANGELL - 1bdDupShed

V in E-W Roof
shear (k) = 7.77 (Wind)

Wall	TW (ft)	V (k)	L (ft)	v (plf)	SW Type	h (ft)	Mot (k-ft)	TW (ft)	DLfloor(psf)	Wfl (plf)	DLwall (psf)	Wwall (plf)	Mr (k-ft)	.6Mr (k-ft)	FS	T (lbs)	Holdowns	Wall
A	17.5	3.89	19	204	SWA													A
D	17.5	3.89	19	204	SWA													D
35																		

Holdowns

V in E-W	Roof																	
Wall	L (ft)	h (ft)	Mot (k-ft)	TW (ft)	DLroof (psf)	Wfl (plf)	DLwall (psf)	Wwall (plf)	Mr (k-ft)	.6Mr (k-ft)	FS	T (lbs)	Holdowns	Wall	C (lbs)			
v=	204	plf																
A1	4.75	10	9.71	10.5	18	189	10	100	3	2.0	0.20	1633	4	A1	2045			
A2	4.75	10	9.71	10.5	18	189	10	100	3	2.0	0.20	1633	4	A2	2045			
A3	4.75	10	9.71	10.5	18	189	10	100	3	2.0	0.20	1633	4	A3	2045			
A4	4.75	10	9.71	10.5	18	189	10	100	3	2.0	0.20	1633	4	A4	2045			
v=	204	plf																
D1	3.75	12	9.20	10.5	18	189	10	120	2	1.3	0.14	2106	4	D1	2454			
D2	5.75	12	14.11	10.5	18	189	10	120	5	3.1	0.22	1921	4	D2	2454			
D3	5.75	12	14.11	10.5	18	189	10	120	5	3.1	0.22	1921	4	D3	2454			
D4	3.75	12	9.20	10.5	18	189	10	120	2	1.3	0.14	2106	4	D4	2454			