



08.29.2025

Structural Calculations for

SOUTHEAST ALASKA REGIONAL HEALTH CONSORTIUM

WRANGELL STAFF HOUSING

SINGLE FAMILY TWO STORY (SHED ROOF)

1064 Zimovia Hwy, Wrangell AK 99929

Prepared by:

Asrade Mengstu PE


Reviewed by:

Kevin Feldman PE



## DESIGN LOADS AND CRITERIA

- 1) GRAVITY LOADS:
  - a) ROOF LOADS:
    1. ROOF DEAD LOAD: 18 psf
    2. ROOF LIVE LOAD: 20 psf
  - b) FLOOR LOADS:
    1. FLOOR DEAD LOAD: 15 psf
    2. FLOOR LIVE LOAD: 40 psf (RESIDENTIAL — ONE- AND TWO- FAMILY DWELLINGS — ALL OTHER AREAS EXCEPT STAIRS)
    3. FLOOR LIVE LOAD: 60 psf (BALCONIES AND DECKS)
  - c) SLABS ON GRADE:
    1. SLABS ON GRADE LIVE LOAD: 40 psf
- 2) HANDRAIL AND GUARDRAIL SYSTEM LOADS:
  - a) CONCENTRATED LOAD: 200 lb (HANDRAIL OR TOP RAIL)
  - b) CONCENTRATED LOAD: 50 lb (INTERMEDIATE RAIL)
  - c) LINEAR LOAD: 50 lb/ft (HANDRAIL OR TOP RAIL)
- 3) SNOW LOADS:
  - a) GROUND SNOW LOAD:  $P_g = 60$  psf,  $I_s = 1.00$ ,  $C_e = 1.0$ ,  $C_t = 1.0$ ,  $C_s = 1.0$
  - b) FLAT ROOF SNOW LOAD:  $P_f = 42$  psf UNIFORM + DRIFT
- 4) WIND CRITERIA:
  - a) 3-SEC PEAK GUST WIND SPEED = 139 mph
  - b) RISK CATEGORY = II
  - c)  $I_w = 1.00$
  - d) EXPOSURE = D
  - e) INTERNAL PRESSURE COEFFICIENT ( $GC_{pi}$ ):  $\pm 0.18$
  - f) EXTERNAL ROOF COMPONENTS & CLADDING: 75 psf MINIMUM (ULTIMATE)
  - g) EXTERNAL WALL COMPONENTS & CLADDING: 80 psf MINIMUM (ULTIMATE)
  - h) STEEL ROOF JOIST NET UPLIFT - PERIMETER 20 FT: 50 psf MINIMUM (ULTIMATE)
  - i) INTERSTORY DRIFT LIMIT =  $1/400$
- 5) SEISMIC CRITERIA:
  - a)  $SS = 0.249$  g /  $S_1 = 0.254$  g MAPPED MCER VALUES
  - b) RISK CATEGORY = II
  - c) PROJECT SITE CLASS = B
  - d)  $I_e = 1.00$
  - e)  $SDS = 0.149$  g /  $SD_1 = 0.136$  g DESIGN RESPONSE COEFFICIENT
  - f) SEISMIC DESIGN CATEGORY = C
  - g) ANALYSIS PROCEDURE: EQUIVALENT LATERAL FORCE PROCEDURE
  - h) SEISMIC FORCE-RESISTING SYSTEM: BEARING WALL SYSTEMS: LIGHT-FRAME (WOOD) WALLS SHEATHED WITH WOOD STRUCTURAL PANELS RATED FOR SHEAR RESISTANCE,  $R = 6.5$
  - i) REDUNDANCY FACTOR: PLAN N-S  $RHO = 1.3$  / PLAN E-W  $RHO = 1.3$
  - j) SEISMIC RESPONSE COEFFICIENT  $C_s = 0.03$
  - k) SEISMIC BASE SHEAR  $V = 1.9$  kips (ULTIMATE)
  - l) ALLOWABLE STORY DRIFT  $\Delta = 0.020h_{sx}$
- 6) FOOTING BEARING PRESSURE: 3000 psf ON APPROVED SUBGRADE, SEE SECTION FOUNDATIONS
- 7) SOIL FRICTION COEFFICIENT: 0.4
- 8) LATERAL SOIL PRESSURE:
  - a) ACTIVE EQUIVALENT FLUID PRESSURE: 35 pcf
  - b) AT-REST EQUIVALENT FLUID PRESSURE: 55 pcf
  - c) PASSIVE EQUIVALENT FLUID PRESSURE: 400 pcf
- 9) FROST DEPTH: 32 INCHES TOP OF FOOTING



1  
 S103  
 UPPER ROOF FRAMING PLAN  
 1/4" = 1'-0"



## Snow Loads : ASCE 7- 16

## Nominal Snow Forces

Roof slope = 3.6 deg  
 Horiz. eave to ridge dist (W) = 26.0 ft  
 Roof length parallel to ridge (L) = 41.0 ft

Type of Roof Monoslope  
 Ground Snow Load Pg = 60.0 psf  
 Risk Category = II  
 Importance Factor I = 1.0  
 Thermal Factor Ct = 1.00  
 Exposure Factor Ce = 1.0

Pf =  $0.7 \cdot Ce \cdot Ct \cdot I \cdot Pg$  = 42.0 psf  
 Unobstructed Slippery Surface no

Sloped-roof Factor Cs = 1.00  
 Balanced Snow Load = **42.0 psf**

Rain on Snow Surcharge Angle 0.52 deg  
 Code Maximum Rain Surcharge 5.0 psf  
 Rain on Snow Surcharge = 0.0 psf  
 Ps plus rain surcharge = 42.0 psf  
 Minimum Snow Load Pm = 20.0 psf

Uniform Roof Design Snow Load = **42.0 psf**


Near ground level surface balanced snow load = **60.0 psf**

NOTE: Alternate spans of continuous beams shall be loaded with half the design roof snow load so as to produce the greatest possible effect - see code for loading diagrams and exceptions for gable roofs..



Roof, Roof: Joist RJ1

1 piece(s) 11 7/8" TJI® 210 @ 24" OC



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	1696 @ 15' 2 1/4"	2472 (3.50")	Passed (69%)	1.15	1.0 D + 1.0 S (Adj Spans)
Shear (lbs)	786 @ 15' 1/2"	1903	Passed (41%)	1.15	1.0 D + 1.0 S (Adj Spans)
Moment (Ft-lbs)	-2048 @ 15' 2 1/4"	4364	Passed (47%)	1.15	1.0 D + 1.0 S (Adj Spans)
Live Load Defl. (in)	0.128 @ 8' 2 5/8"	0.433	Passed (L/999+)	--	1.0 D + 1.0 S (Alt Spans)
Total Load Defl. (in)	0.166 @ 8' 2"	0.649	Passed (L/941)	--	1.0 D + 1.0 S (Alt Spans)

- Deflection criteria: LL (L/360) and TL (L/240).
- Overhang deflection criteria: LL (2L/360) and TL (2L/240).
- Allowed moment does not reflect the adjustment for the beam stability factor.

Member Length : 28' 10 15/16"  
System : Roof  
Member Type : Joist  
Building Use : Residential  
Building Code : IBC 2018  
Design Methodology : ASD  
Member Pitch : 0.75/12

Supports	Bearing Length			Loads to Supports (lbs)				Accessories	Details
	Total	Available	Required	Dead	Roof Live	Snow	Factored		
1 - Beveled Plate - DF	5.50"	5.50"	3.50"	227	314	659	886	Blocking	R1
2 - Beveled Plate - SPF	3.50"	3.50"	3.50"	440	598	1256	1696	None	R7
3 - Beveled Plate - DF	5.50"	5.50"	3.50"	198	284	595	794	Blocking	R1

Blocking Panels are assumed to carry no loads applied directly above them and the full load is applied to the member being designed.

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	6' o/c	
Bottom Edge (Lu)	5' 2" o/c	

- TJI joists are only analyzed using Maximum Allowable bracing solutions.
- Maximum allowable bracing intervals based on applied load.
- Dimensions for lateral bracing intervals are measured along the length of the member for sloped conditions.

Vertical Load	Location	Spacing	Dead (0.90)	Roof Live (1.25)	Snow (1.15)	Comments
1 - Uniform (PSF)	0 to 28' 9 1/2"	24"	15.0	20.0	42.0	Default Load

### Weyerhaeuser Notes



Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to [www.weyerhaeuser.com/woodproducts/document-library](http://www.weyerhaeuser.com/woodproducts/document-library).

The product application, input design loads, dimensions and support information have been provided by ForteWEB Software Operator



ForteWEB Software Operator	Job Notes
Asrade Mengstu Cushing Terrell (406) 500-3544 asrademengstu@cushingterrell.com	

Shear blocking:

1 1/8" TJ® Rim Board (with depths ≤ 16"),  
 1 1/4" or 1 1/2" TimberStrand® LSL  
 or TJI® joist.



**INTERMEDIATE BEARING**  
*Blocking panels or shear blocking may be  
 specified for joist stability at intermediate supports*



ForteWEB Software Operator	Job Notes
Asrade Mengstu Cushing Terrell (406) 500-3544 asrademengstu@cushingterrell.com	




8/30/2025 4:11:42 AM UTC

ForteWEB v3.9

File Name: SEARHC Wrangell 2bdrm2stryShed

Roof, Roof Header Beam RH1  
1 piece(s) 4 x 10 DF No.2



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	2070 @ 1' 1/2"	6563 (3.00")	Passed (32%)	--	1.0 D + 1.0 S (All Spans)
Shear (lbs)	1625 @ 1' 1/4"	4468	Passed (36%)	1.15	1.0 D + 1.0 S (All Spans)
Moment (Ft-lbs)	4660 @ 4' 9"	5166	Passed (90%)	1.15	1.0 D + 1.0 S (All Spans)
Live Load Defl. (in)	0.140 @ 4' 9"	0.463	Passed (L/790)	--	1.0 D + 1.0 S (All Spans)
Total Load Defl. (in)	0.194 @ 4' 9"	0.617	Passed (L/571)	--	1.0 D + 1.0 S (All Spans)

- Deflection criteria: LL (L/240) and TL (L/180).
- Allowed moment does not reflect the adjustment for the beam stability factor.
- Applicable calculations are based on NDS.

Member Length : 9' 6"  
System : Roof  
Member Type : Drop Beam  
Building Use : Residential  
Building Code : IBC 2018  
Design Methodology : ASD  
Member Pitch : 0/12

Supports	Bearing Length			Loads to Supports (lbs)				Accessories
	Total	Available	Required	Dead	Roof Live	Snow	Factored	
1 - Trimmer - DF	3.00"	3.00"	1.50"	573	713	1496	2070	None
2 - Trimmer - DF	3.00"	3.00"	1.50"	573	713	1496	2070	None

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	9' 6" o/c	
Bottom Edge (Lu)	9' 6" o/c	

- Maximum allowable bracing intervals based on applied load.

Vertical Loads	Location (Side)	Tributary Width	Dead (0.90)	Roof Live (1.25)	Snow (1.15)	Comments
0 - Self Weight (PLF)	0 to 9' 6"	N/A	8.2	--	--	
1 - Uniform (PSF)	0 to 9' 6" (Front)	7' 6"	15.0	20.0	42.0	Default Load

- Side loads are assumed to not induce cross-grain tension.

#### Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to [www.weyerhaeuser.com/woodproducts/document-library](http://www.weyerhaeuser.com/woodproducts/document-library).


The product application, input design loads, dimensions and support information have been provided by ForteWEB Software Operator

ForteWEB Software Operator	Job Notes
Asrade Mengstu Cushing Terrell (406) 500-3544 asrademengstu@cushingterrell.com	

Roof, Roof Header Beam RH2

1 piece(s) 4 x 8 DF No.2

Overall Length: 6' 6"



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	1503 @ 1 1/2"	6563 (3.00")	Passed (23%)	--	1.0 D + 1.0 S (All Spans)
Shear (lbs)	1108 @ 10 1/4"	3502	Passed (32%)	1.15	1.0 D + 1.0 S (All Spans)
Moment (Ft-lbs)	2258 @ 3' 3"	3438	Passed (66%)	1.15	1.0 D + 1.0 S (All Spans)
Live Load Defl. (in)	0.065 @ 3' 3"	0.313	Passed (L/999+)	--	1.0 D + 1.0 S (All Spans)
Total Load Defl. (in)	0.089 @ 3' 3"	0.417	Passed (L/840)	--	1.0 D + 1.0 S (All Spans)

- Deflection criteria: LL (L/240) and TL (L/180).
- Allowed moment does not reflect the adjustment for the beam stability factor.
- Applicable calculations are based on NDS.

Member Length : 6' 6"  
System : Roof  
Member Type : Drop Beam  
Building Use : Residential  
Building Code : IBC 2018  
Design Methodology : ASD  
Member Pitch : 0/12

Supports	Bearing Length			Loads to Supports (lbs)				Accessories
	Total	Available	Required	Dead	Roof Live	Snow	Factored	
1 - Trimmer - DF	3.00"	3.00"	1.50"	411	520	1092	1503	None
2 - Trimmer - DF	3.00"	3.00"	1.50"	411	520	1092	1503	None

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	6' 6" o/c	
Bottom Edge (Lu)	6' 6" o/c	

- Maximum allowable bracing intervals based on applied load.

Vertical Loads	Location (Side)	Tributary Width	Dead (0.90)	Roof Live (1.25)	Snow (1.15)	Comments
0 - Self Weight (PLF)	0 to 6' 6"	N/A	6.4	--	--	
1 - Uniform (PSF)	0 to 6' 6" (Front)	8'	15.0	20.0	42.0	Default Load

- Side loads are assumed to not induce cross-grain tension.

### Weyerhaeuser Notes


Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to [www.weyerhaeuser.com/woodproducts/document-library](http://www.weyerhaeuser.com/woodproducts/document-library).

The product application, input design loads, dimensions and support information have been provided by ForteWEB Software Operator

ForteWEB Software Operator	Job Notes
Asrade Mengstu Cushing Terrell (406) 500-3544 asrademengstu@cushingterrell.com	

Roof, Roof Header Beam RH3

1 piece(s) 4 x 8 DF No.2



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	809 @ 1' 1/2"	6563 (3.00")	Passed (12%)	--	1.0 D + 1.0 S (All Spans)
Shear (lbs)	414 @ 10 1/4"	3502	Passed (12%)	1.15	1.0 D + 1.0 S (All Spans)
Moment (Ft-lbs)	611 @ 1' 9"	3438	Passed (18%)	1.15	1.0 D + 1.0 S (All Spans)
Live Load Defl. (in)	0.005 @ 1' 9"	0.162	Passed (L/999+)	--	1.0 D + 1.0 S (All Spans)
Total Load Defl. (in)	0.007 @ 1' 9"	0.217	Passed (L/999+)	--	1.0 D + 1.0 S (All Spans)

- Deflection criteria: LL (L/240) and TL (L/180).
- Allowed moment does not reflect the adjustment for the beam stability factor.
- Applicable calculations are based on NDS.

Member Length : 3' 6"  
System : Roof  
Member Type : Drop Beam  
Building Use : Residential  
Building Code : IBC 2018  
Design Methodology : ASD  
Member Pitch : 0/12

Supports	Bearing Length			Loads to Supports (lbs)				Accessories
	Total	Available	Required	Dead	Roof Live	Snow	Factored	
1 - Trimmer - DF	3.00"	3.00"	1.50"	221	280	588	809	None
2 - Trimmer - DF	3.00"	3.00"	1.50"	221	280	588	809	None

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	3' 6" o/c	
Bottom Edge (Lu)	3' 6" o/c	

- Maximum allowable bracing intervals based on applied load.

Vertical Loads	Location (Side)	Tributary Width	Dead (0.90)	Roof Live (1.25)	Snow (1.15)	Comments
0 - Self Weight (PLF)	0 to 3' 6"	N/A	6.4	--	--	
1 - Uniform (PSF)	0 to 3' 6" (Front)	8'	15.0	20.0	42.0	Default Load

- Side loads are assumed to not induce cross-grain tension.

### Weyerhaeuser Notes


Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to [www.weyerhaeuser.com/woodproducts/document-library](http://www.weyerhaeuser.com/woodproducts/document-library).

The product application, input design loads, dimensions and support information have been provided by ForteWEB Software Operator

ForteWEB Software Operator	Job Notes
Asrade Mengstu Cushing Terrell (406) 500-3544 asrademengstu@cushingterrell.com	

Roof, Roof Header Beam RH4

1 piece(s) 4 x 8 DF No.2



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	843 @ 1 1/2"	6563 (3.00")	Passed (13%)	--	1.0 D + 1.0 S (All Spans)
Shear (lbs)	691 @ 10 1/4"	3502	Passed (20%)	1.15	1.0 D + 1.0 S (All Spans)
Moment (Ft-lbs)	1898 @ 4' 9"	3438	Passed (55%)	1.15	1.0 D + 1.0 S (All Spans)
Live Load Defl. (in)	0.117 @ 4' 9"	0.463	Passed (L/951)	--	1.0 D + 1.0 S (All Spans)
Total Load Defl. (in)	0.164 @ 4' 9"	0.617	Passed (L/675)	--	1.0 D + 1.0 S (All Spans)

- Deflection criteria: LL (L/240) and TL (L/180).
- Allowed moment does not reflect the adjustment for the beam stability factor.
- Applicable calculations are based on NDS.

Member Length : 9' 6"  
System : Roof  
Member Type : Drop Beam  
Building Use : Residential  
Building Code : IBC 2018  
Design Methodology : ASD  
Member Pitch : 0/12

Supports	Bearing Length			Loads to Supports (lbs)				Accessories
	Total	Available	Required	Dead	Roof Live	Snow	Factored	
1 - Trimmer - DF	3.00"	3.00"	1.50"	244	285	599	843	None
2 - Trimmer - DF	3.00"	3.00"	1.50"	244	285	599	843	None

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	9' 6" o/c	
Bottom Edge (Lu)	9' 6" o/c	

- Maximum allowable bracing intervals based on applied load.

Vertical Loads	Location (Side)	Tributary Width	Dead (0.90)	Roof Live (1.25)	Snow (1.15)	Comments
0 - Self Weight (PLF)	0 to 9' 6"	N/A	6.4	--	--	
1 - Uniform (PSF)	0 to 9' 6" (Front)	3'	15.0	20.0	42.0	Default Load

- Side loads are assumed to not induce cross-grain tension.

### Weyerhaeuser Notes


Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to [www.weyerhaeuser.com/woodproducts/document-library](http://www.weyerhaeuser.com/woodproducts/document-library).

The product application, input design loads, dimensions and support information have been provided by ForteWEB Software Operator

ForteWEB Software Operator	Job Notes
Asrade Mengstu Cushing Terrell (406) 500-3544 asrademengstu@cushingterrell.com	

Roof, Roof Header Beam RH5

1 piece(s) 4 x 8 DF No.2



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	1208 @ 1 1/2"	6563 (3.00")	Passed (18%)	--	1.0 D + 1.0 S (All Spans)
Shear (lbs)	619 @ 10 1/4"	3502	Passed (18%)	1.15	1.0 D + 1.0 S (All Spans)
Moment (Ft-lbs)	912 @ 1' 9"	3438	Passed (27%)	1.15	1.0 D + 1.0 S (All Spans)
Live Load Defl. (in)	0.007 @ 1' 9"	0.162	Passed (L/999+)	--	1.0 D + 1.0 S (All Spans)
Total Load Defl. (in)	0.010 @ 1' 9"	0.217	Passed (L/999+)	--	1.0 D + 1.0 S (All Spans)

- Deflection criteria: LL (L/240) and TL (L/180).
- Allowed moment does not reflect the adjustment for the beam stability factor.
- Applicable calculations are based on NDS.

Member Length : 3' 6"  
System : Roof  
Member Type : Drop Beam  
Building Use : Residential  
Building Code : IBC 2018  
Design Methodology : ASD  
Member Pitch : 0/12

Supports	Bearing Length			Loads to Supports (lbs)				Accessories
	Total	Available	Required	Dead	Roof Live	Snow	Factored	
1 - Trimmer - DF	3.00"	3.00"	1.50"	326	420	882	1208	None
2 - Trimmer - DF	3.00"	3.00"	1.50"	326	420	882	1208	None

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	3' 6" o/c	
Bottom Edge (Lu)	3' 6" o/c	

- Maximum allowable bracing intervals based on applied load.

Vertical Loads	Location (Side)	Tributary Width	Dead (0.90)	Roof Live (1.25)	Snow (1.15)	Comments
0 - Self Weight (PLF)	0 to 3' 6"	N/A	6.4	--	--	
1 - Uniform (PSF)	0 to 3' 6" (Front)	12'	15.0	20.0	42.0	Default Load


- Side loads are assumed to not induce cross-grain tension.

### Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to [www.weyerhaeuser.com/woodproducts/document-library](http://www.weyerhaeuser.com/woodproducts/document-library).

The product application, input design loads, dimensions and support information have been provided by ForteWEB Software Operator

ForteWEB Software Operator	Job Notes
Asrade Mengstu Cushing Terrell (406) 500-3544 asrademengstu@cushingterrell.com	



1  
S102

## SECOND LEVEL AND LOW ROOF FRAMING PLAN

1/4" = 1'-0"




NORTH REF



2nd Floor, Floor Beam FB1

1 piece(s) 3 1/2" x 11 7/8" 24F-V8 DF Glulam



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	1717 @ 3 1/2"	3413 (1.50")	Passed (50%)	--	1.0 D + 1.0 L (All Spans)
Shear (lbs)	1054 @ 1' 3 3/8"	7343	Passed (14%)	1.00	1.0 D + 1.0 L (All Spans)
Pos Moment (Ft-lbs)	2200 @ 2' 10 1/4"	16452	Passed (13%)	1.00	1.0 D + 1.0 L (All Spans)
Live Load Defl. (in)	0.008 @ 2' 10 1/4"	0.171	Passed (L/999+)	--	1.0 D + 1.0 L (All Spans)
Total Load Defl. (in)	0.012 @ 2' 10 1/4"	0.256	Passed (L/999+)	--	1.0 D + 1.0 L (All Spans)

Member Length : 5' 3 1/2"

System : Floor

Member Type : Drop Beam

Building Use : Residential

Building Code : IBC 2018

Design Methodology : ASD

- Deflection criteria: LL (L/360) and TL (L/240).
- Allowed moment does not reflect the adjustment for the beam stability factor.
- Volume factor of 1.00 was calculated for positive bending using length L = 5' 1 1/2".
- The effects of positive or negative camber have not been accounted for when calculating deflection.
- Applicable calculations are based on NDS.

Supports	Bearing Length			Loads to Supports (lbs)			Accessories
	Total	Available	Required	Dead	Floor Live	Factored	
1 - Hanger on 11 7/8" GLB beam	3.50"	Hanger <sup>1</sup>	1.50"	540	1370	1910	See note <sup>1</sup>
2 - Column - DF	3.50"	3.50"	1.50"	519	1310	1829	Blocking

- Blocking Panels are assumed to carry no loads applied directly above them and the full load is applied to the member being designed.
- At hanger supports, the Total Bearing dimension is equal to the width of the material that is supporting the hanger
- <sup>1</sup> See Connector grid below for additional information and/or requirements.

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	5' 4" o/c	
Bottom Edge (Lu)	5' 4" o/c	

- Maximum allowable bracing intervals based on applied load.

#### Connector: Simpson Strong-Tie

Support	Model	Seat Length	Top Fasteners	Face Fasteners	Member Fasteners	Accessories
1 - Face Mount Hanger	LUS410	2.00"	N/A	8-16d	6-16d	

- Refer to manufacturer notes and instructions for proper installation and use of all connectors.

Vertical Loads	Location (Side)	Tributary Width	Dead (0.90)	Floor Live (1.00)	Comments
0 - Self Weight (PLF)	3 1/2" to 5' 7"	N/A	10.1	--	
1 - Uniform (PSF)	0 to 5' 7" (Front)	12'	15.0	40.0	Default Load

- Side loads are assumed to not induce cross-grain tension.


#### Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to [www.weyerhaeuser.com/woodproducts/document-library](http://www.weyerhaeuser.com/woodproducts/document-library).

The product application, input design loads, dimensions and support information have been provided by ForteWEB Software Operator

ForteWEB Software Operator	Job Notes
Asrade Mengstu Cushing Terrell (406) 500-3544 asrademengstu@cushingterrell.com	

2nd Floor, Floor Beam FB2  
1 piece(s) 5 1/2" x 11 7/8" 24F-V8 DF Glulam



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	3364 @ 15' 1"	19663 (5.50")	Passed (17%)	--	1.0 D + 0.75 L + 0.75 S (All Spans)
Shear (lbs)	2969 @ 13' 11 5/8"	13269	Passed (22%)	1.15	1.0 D + 0.75 L + 0.75 S (All Spans)
Pos Moment (Ft-lbs)	9263 @ 8' 6 15/16"	29731	Passed (31%)	1.15	1.0 D + 0.75 L + 0.75 S (All Spans)
Live Load Defl. (in)	0.169 @ 7' 11 1/16"	0.738	Passed (L/999+)	--	1.0 D + 0.75 L + 0.75 S (All Spans)
Total Load Defl. (in)	0.268 @ 7' 11"	0.983	Passed (L/661)	--	1.0 D + 0.75 L + 0.75 S (All Spans)

- Deflection criteria: LL (L/240) and TL (L/180).
- Allowed moment does not reflect the adjustment for the beam stability factor.
- Volume factor of 1.00 was calculated for positive bending using length L = 14' 9".
- The effects of positive or negative camber have not been accounted for when calculating deflection.
- Applicable calculations are based on NDS.

Member Length : 15' 5"  
System : Roof  
Member Type : Drop Beam  
Building Use : Residential  
Building Code : IBC 2018  
Design Methodology : ASD  
Member Pitch : 0/12

Supports	Bearing Length			Loads to Supports (lbs)					Accessories
	Total	Available	Required	Dead	Floor Live	Roof Live	Snow	Factored	
1 - Column - DF	5.50"	5.50"	1.50"	875	516	617	1434	2337	None
2 - Column - DF	5.50"	5.50"	1.50"	1230	1411	617	1434	3364	None

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	15' 5" o/c	
Bottom Edge (Lu)	15' 5" o/c	

•Maximum allowable bracing intervals based on applied load.

Vertical Loads	Location (Side)	Tributary Width	Dead (0.90)	Floor Live (1.00)	Roof Live (1.25)	Snow (1.15)	Comments
0 - Self Weight (PLF)	0 to 15' 5"	N/A	15.9	--	--	--	
1 - Uniform (PSF)	0 to 15' 5" (Front)	1'	18.0	--	20.0	60.0	Default Load
2 - Uniform (PSF)	0 to 15' 5" (Front)	3'	18.0	--	20.0	42.0	Default Load
3 - Uniform (PSF)	0 to 15' 5" (Front)	1'	15.0	40.0	--	--	Default Load
4 - Point (lb)	12' 9" (Front)	N/A	519	1310	--	--	Linked from: Floor Beam FB1, Support 2

• Side loads are assumed to not induce cross-grain tension.


### Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to [www.weyerhaeuser.com/woodproducts/document-library](http://www.weyerhaeuser.com/woodproducts/document-library).

The product application, input design loads, dimensions and support information have been provided by ForteWEB Software Operator

ForteWEB Software Operator	Job Notes
Asrade Mengstu Cushing Terrell (406) 500-3544 asrademengstu@cushingterrell.com	

2nd Floor, Roof: Joist RJ1  
1 piece(s) 2 x 8 DF No.2 @ 24" OC



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	456 @ 7' 5 1/2"	1406 (1.50")	Passed (32%)	--	1.0 D + 1.0 S (Alt Spans)
Shear (lbs)	366 @ 6' 10 1/4"	1501	Passed (24%)	1.15	1.0 D + 1.0 S (Alt Spans)
Moment (Ft-lbs)	694 @ 4' 5"	1564	Passed (44%)	1.15	1.0 D + 1.0 S (Alt Spans)
Live Load Defl. (in)	0.051 @ 4' 4 3/8"	0.312	Passed (L/999+)	--	1.0 D + 1.0 S (Alt Spans)
Total Load Defl. (in)	0.063 @ 4' 4 7/16"	0.415	Passed (L/999+)	--	1.0 D + 1.0 S (Alt Spans)

Member Length : 7' 5 1/2"  
System : Roof  
Member Type : Joist  
Building Use : Residential  
Building Code : IBC 2018  
Design Methodology : ASD  
Member Pitch : 0.25/12

- Deflection criteria: LL (L/240) and TL (L/180).
- Overhang deflection criteria: LL (2L/240) and TL (2L/180).
- Allowed moment does not reflect the adjustment for the beam stability factor.
- A 15% increase in the moment capacity has been added to account for repetitive member usage.
- Applicable calculations are based on NDS.

Supports	Bearing Length			Loads to Supports (lbs)				Accessories
	Total	Available	Required	Dead	Roof Live	Snow	Factored	
1 - Beveled Plate - DF	5.50"	5.50"	1.50"	134	179	536	670	Blocking
2 - Hanger on 7 1/4" DF Ledger	1.50"	Hanger <sup>1</sup>	1.50"	94	127	381	475	See note <sup>1</sup>

- Blocking Panels are assumed to carry no loads applied directly above them and the full load is applied to the member being designed.
- At hanger supports, the Total Bearing dimension is equal to the width of the material that is supporting the hanger
- <sup>1</sup> See Connector grid below for additional information and/or requirements.

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	7' 6" o/c	
Bottom Edge (Lu)	7' 6" o/c	

- Maximum allowable bracing intervals based on applied load.

#### Connector: Simpson Strong-Tie

Support	Model	Seat Length	Top Fasteners	Face Fasteners	Member Fasteners	Accessories
2 - Face Mount Hanger	LRU26Z	1.94"	N/A	4-10dx1.5	5-10d	

- Refer to manufacturer notes and instructions for proper installation and use of all connectors.

Vertical Load	Location (Side)	Spacing	Dead (0.90)	Roof Live (1.25)	Snow (1.15)	Comments
1 - Uniform (PSF)	0 to 7' 7"	24"	15.0	20.0	60.0	Default Load


#### Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to [www.weyerhaeuser.com/woodproducts/document-library](http://www.weyerhaeuser.com/woodproducts/document-library).

The product application, input design loads, dimensions and support information have been provided by ForteWEB Software Operator

ForteWEB Software Operator	Job Notes
Asrade Mengstu Cushing Terrell (406) 500-3544 asrademengstu@cushingterrell.com	

2nd Floor, Roof: Joist RJ2  
2 piece(s) 11 7/8" TJI® 560 @ 16" OC



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	1331 @ 28' 11 1/2"	2910 (1.75")	Passed (46%)	1.15	1.0 D + 1.0 S (Alt Spans)
Shear (lbs)	1331 @ 28' 11 1/2"	4715	Passed (28%)	1.15	1.0 D + 1.0 S (Alt Spans)
Moment (Ft-lbs)	8860 @ 15' 7 13/16"	21850	Passed (41%)	1.15	1.0 D + 1.0 S (Alt Spans)
Live Load Defl. (in)	0.774 @ 15' 7 5/16"	0.893	Passed (L/415)	--	1.0 D + 1.0 S (Alt Spans)
Total Load Defl. (in)	0.966 @ 15' 7 3/8"	1.339	Passed (L/333)	--	1.0 D + 1.0 S (Alt Spans)

Member Length : 29' 15/16"  
System : Roof  
Member Type : Joist  
Building Use : Residential  
Building Code : IBC 2018  
Design Methodology : ASD  
Member Pitch : 0.75/12

- Deflection criteria: LL (L/360) and TL (L/240).
- Overhang deflection criteria: LL (2L/360) and TL (2L/240).
- Upward deflection on left cantilever exceeds overhang deflection criteria.
- Allowed moment does not reflect the adjustment for the beam stability factor.

Supports	Bearing Length			Loads to Supports (lbs)				Accessories	Details
	Total	Available	Required	Dead	Roof Live	Snow	Factored		
1 - Beveled Plate - DF	5.50"	5.50"	3.50"	314	418	1255	1569	Blocking	R1
2 - Hanger on 11 7/8" GLB beam	5.50"	Hanger <sup>1</sup>	1.75" / - <sup>2</sup>	275	367	1102	1377	See note <sup>1</sup>	W

- Blocking Panels are assumed to carry no loads applied directly above them and the full load is applied to the member being designed.
- At hanger supports, the Total Bearing dimension is equal to the width of the material that is supporting the hanger
- <sup>1</sup> See Connector grid below for additional information and/or requirements.
- <sup>2</sup> Required Bearing Length / Required Bearing Length with Web Stiffeners

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	8' 5" o/c	
Bottom Edge (Lu)	14' 7" o/c	

- TJI joists are only analyzed using Maximum Allowable bracing solutions.
- Maximum allowable bracing intervals based on applied load.
- Dimensions for lateral bracing intervals are measured along the length of the member for sloped conditions.

**Connector: Simpson Strong-Tie**

Support	Model	Seat Length	Top Fasteners	Face Fasteners	Member Fasteners	Accessories
2 - Face Mount Hanger	HU410-2X SLD3	2.50"	N/A	14-10dx1.5	6-10d	Web Stiffeners

- Refer to manufacturer notes and instructions for proper installation and use of all connectors.

Vertical Load	Location	Spacing	Dead (0.90)	Roof Live (1.25)	Snow (1.15)	Comments
1 - Uniform (PSF)	0 to 29' 5"	16"	15.0	20.0	60.0	Default Load

**Weyerhaeuser Notes**


Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to [www.weyerhaeuser.com/woodproducts/document-library](http://www.weyerhaeuser.com/woodproducts/document-library).

The product application, input design loads, dimensions and support information have been provided by ForteWEB Software Operator

ForteWEB Software Operator	Job Notes
Asrade Mengstu Cushing Terrell (406) 500-3544 asrademengstu@cushingterrell.com	


Shear blocking:

1 1/8" TJ® Rim Board (with depths ≤ 16"),  
 1 1/4" or 1 1/2" TimberStrand® LSL  
 or TJ® joist.



R1 R1W

#### WEB STIFFENER ATTACHMENT



TJI® Joist Series	Depth (in.)	Minimum Web Stiffener Size	Nailing Requirements		
			Type	Number Nails	
				End	Intermediate
110 210 230 & 360	All All All	5/8" x 2 5/16" (1) 3/4" x 2 5/16" (1) 7/8" x 2 5/16" (1)	8d (0.113" x 2 1/2")	3	3
560	All	2x4 (2)	16d (0.135" x 3 1/2")		
560D	18"	2x4 (2)	16d (0.135" x 3 1/2")	4	4
	20"			5	5
	22" (3)			6	11
	24" (3)			6	13

(1) PS1 or PS2 sheathing, face grain vertical

(2) Construction grade or better

(3) Web stiffeners are always required for 22" and 24" TJI® 560D Joists

W

ForteWEB Software Operator	Job Notes
Asrade Mengstu Cushing Terrell (406) 500-3544 asrademengstu@cushingterrell.com	




8/30/2025 4:13:02 AM UTC

ForteWEB v3.9

File Name: SEARHC Wrangell 2bdrm2stryShed

2nd Floor, Roof Joist RJ3  
1 piece(s) 11 7/8" TJI® 210 @ 16" OC



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	323 @ 5 1/2"	1156 (1.75")	Passed (28%)	1.15	1.0 D + 1.0 S (Alt Spans)
Shear (lbs)	323 @ 5 1/2"	1903	Passed (17%)	1.15	1.0 D + 1.0 S (Alt Spans)
Moment (Ft-lbs)	688 @ 4' 8 9/16"	4364	Passed (16%)	1.15	1.0 D + 1.0 S (Alt Spans)
Live Load Defl. (in)	0.032 @ 4' 9 9/16"	0.291	Passed (L/999+)	--	1.0 D + 1.0 S (Alt Spans)
Total Load Defl. (in)	0.043 @ 4' 9 7/16"	0.436	Passed (L/999+)	--	1.0 D + 1.0 S (Alt Spans)

- Deflection criteria: LL (L/360) and TL (L/240).
- Overhang deflection criteria: LL (2L/360) and TL (2L/240).
- Allowed moment does not reflect the adjustment for the beam stability factor.

Member Length : 10' 5 1/2"  
System : Roof  
Member Type : Joist  
Building Use : Residential  
Building Code : IBC 2018  
Design Methodology : ASD  
Member Pitch : 0/12

Supports	Bearing Length			Loads to Supports (lbs)				Accessories
	Total	Available	Required	Dead	Roof Live	Snow	Factored	
1 - Hanger on 11 7/8" GLB beam	5.50"	Hanger <sup>1</sup>	1.75" / - <sup>2</sup>	93	126	265	358	See note <sup>1</sup>
2 - Stud wall - DF	5.50"	5.50"	3.50"	125	167	351	476	Blocking

- Blocking Panels are assumed to carry no loads applied directly above them and the full load is applied to the member being designed.
- At hanger supports, the Total Bearing dimension is equal to the width of the material that is supporting the hanger
- <sup>1</sup> See Connector grid below for additional information and/or requirements.
- <sup>2</sup> Required Bearing Length / Required Bearing Length with Web Stiffeners

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	8' 8" o/c	
Bottom Edge (Lu)	8' 8" o/c	

- TJI joists are only analyzed using Maximum Allowable bracing solutions.
- Maximum allowable bracing intervals based on applied load.

#### Connector: Simpson Strong-Tie

Support	Model	Seat Length	Top Fasteners	Face Fasteners	Member Fasteners	Accessories
1 - Face Mount Hanger	IUS2.06/11.88	2.00"	N/A	10-10dx1.5	2-Strong-Grip	

- Refer to manufacturer notes and instructions for proper installation and use of all connectors.

Vertical Load	Location	Spacing	Dead (0.90)	Roof Live (1.25)	Snow (1.15)	Comments
1 - Uniform (PSF)	0 to 10' 11"	16"	15.0	20.0	42.0	Default Load

#### Weyerhaeuser Notes


Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to [www.weyerhaeuser.com/woodproducts/document-library](http://www.weyerhaeuser.com/woodproducts/document-library).

The product application, input design loads, dimensions and support information have been provided by ForteWEB Software Operator

ForteWEB Software Operator	Job Notes
Asrade Mengstu Cushing Terrell (406) 500-3544 asrademengstu@cushingterrell.com	

2nd Floor, Roof Joist RJ4

1 piece(s) 11 7/8" TJI® 210 @ 16" OC



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	725 @ 6' 2 1/4"	2950 (5.25")	Passed (25%)	1.15	1.0 D + 1.0 S (All Spans)
Shear (lbs)	342 @ 6' 5"	1903	Passed (18%)	1.15	1.0 D + 1.0 S (All Spans)
Moment (Ft-lbs)	-850 @ 6' 2 1/4"	4364	Passed (19%)	1.15	1.0 D + 1.0 S (All Spans)
Live Load Defl. (in)	0.056 @ 10' 11"	0.315	Passed (2L/999+)	--	1.0 D + 1.0 S (Alt Spans)
Total Load Defl. (in)	0.074 @ 10' 11"	0.473	Passed (2L/999+)	--	1.0 D + 1.0 S (Alt Spans)

- Deflection criteria: LL (L/360) and TL (L/240).
- Overhang deflection criteria: LL (2L/360) and TL (2L/240).
- Right cantilever length exceeds 1/3 member length or 1/2 back span length. Additional bracing should be considered.
- Allowed moment does not reflect the adjustment for the beam stability factor.

Member Length : 10' 5 1/2"  
System : Roof  
Member Type : Joist  
Building Use : Residential  
Building Code : IBC 2018  
Design Methodology : ASD  
Member Pitch : 0/12

Supports	Bearing Length			Loads to Supports (lbs)				Accessories
	Total	Available	Required	Dead	Roof Live	Snow	Factored	
1 - Hanger on 11 7/8" GLB beam	5.50"	Hanger <sup>1</sup>	1.75" / - <sup>2</sup>	27	63/-2	131/-3	159	See note <sup>1</sup>
2 - Stud wall - DF	5.50"	5.50"	3.50"	191	255	535	725	Blocking

- Blocking Panels are assumed to carry no loads applied directly above them and the full load is applied to the member being designed.
- At hanger supports, the Total Bearing dimension is equal to the width of the material that is supporting the hanger
- <sup>1</sup> See Connector grid below for additional information and/or requirements.
- <sup>2</sup> Required Bearing Length / Required Bearing Length with Web Stiffeners

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	8' 8" o/c	
Bottom Edge (Lu)	8' 1" o/c	

- TJI joists are only analyzed using Maximum Allowable bracing solutions.
- Maximum allowable bracing intervals based on applied load.

#### Connector: Simpson Strong-Tie

Support	Model	Seat Length	Top Fasteners	Face Fasteners	Member Fasteners	Accessories
1 - Face Mount Hanger	IUS2.06/11.88	2.00"	N/A	10-10dx1.5	2-Strong-Grip	

- Refer to manufacturer notes and instructions for proper installation and use of all connectors.

Vertical Load	Location	Spacing	Dead (0.90)	Roof Live (1.25)	Snow (1.15)	Comments
1 - Uniform (PSF)	0 to 10' 11"	16"	15.0	20.0	42.0	Default Load


#### Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to [www.weyerhaeuser.com/woodproducts/document-library](http://www.weyerhaeuser.com/woodproducts/document-library).

The product application, input design loads, dimensions and support information have been provided by ForteWEB Software Operator

ForteWEB Software Operator	Job Notes
Asrade Mengstu Cushing Terrell (406) 500-3544 asrademengstu@cushingterrell.com	

2nd Floor, Roof Beam RB1  
1 piece(s) 4 x 8 DF No.2



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	881 @ 5' 1/2"	3281 (1.50")	Passed (27%)	--	1.0 D + 1.0 S (All Spans)
Shear (lbs)	696 @ 1' 3/4"	3502	Passed (20%)	1.15	1.0 D + 1.0 S (All Spans)
Moment (Ft-lbs)	1266 @ 3' 4"	3438	Passed (37%)	1.15	1.0 D + 1.0 S (All Spans)
Live Load Defl. (in)	0.033 @ 3' 4"	0.287	Passed (L/999+)	--	1.0 D + 1.0 S (All Spans)
Total Load Defl. (in)	0.042 @ 3' 4"	0.383	Passed (L/999+)	--	1.0 D + 1.0 S (All Spans)

- Deflection criteria: LL (L/240) and TL (L/180).
- Allowed moment does not reflect the adjustment for the beam stability factor.
- Applicable calculations are based on NDS.

Member Length : 5' 9"  
System : Roof  
Member Type : Drop Beam  
Building Use : Residential  
Building Code : IBC 2018  
Design Methodology : ASD  
Member Pitch : 0/12

Supports	Bearing Length			Loads to Supports (lbs)				Accessories
	Total	Available	Required	Dead	Roof Live	Snow	Factored	
1 - Hanger on 7 1/4" GLB beam	5.50"	Hanger <sup>1</sup>	1.50"	218	267	800	1018	See note <sup>1</sup>
2 - Hanger on 7 1/4" GLB beam	5.50"	Hanger <sup>1</sup>	1.50"	218	267	800	1018	See note <sup>1</sup>

- At hanger supports, the Total Bearing dimension is equal to the width of the material that is supporting the hanger
- <sup>1</sup> See Connector grid below for additional information and/or requirements.

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	5' 9" o/c	
Bottom Edge (Lu)	5' 9" o/c	

- Maximum allowable bracing intervals based on applied load.

#### Connector: Simpson Strong-Tie

Support	Model	Seat Length	Top Fasteners	Face Fasteners	Member Fasteners	Accessories
1 - Face Mount Hanger	HU46	2.50"	N/A	8-10dx1.5	4-10d	
2 - Face Mount Hanger	HU46	2.50"	N/A	8-10dx1.5	4-10d	

- Refer to manufacturer notes and instructions for proper installation and use of all connectors.

Vertical Loads	Location (Side)	Tributary Width	Dead (0.90)	Roof Live (1.25)	Snow (1.15)	Comments
0 - Self Weight (PLF)	5' 1/2" to 6' 2 1/2"	N/A	6.4	--	--	
1 - Uniform (PSF)	0 to 6' 8" (Front)	4'	15.0	20.0	60.0	Default Load

- Side loads are assumed to not induce cross-grain tension.

#### Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to [www.weyerhaeuser.com/woodproducts/document-library](http://www.weyerhaeuser.com/woodproducts/document-library).


The product application, input design loads, dimensions and support information have been provided by ForteWEB Software Operator

ForteWEB Software Operator	Job Notes
Asrade Mengstu Cushing Terrell (406) 500-3544 asrademengstu@cushingterrell.com	



2nd Floor, Roof Beam RB2

1 piece(s) 6 3/4" x 10 1/2" 24F-V4 DF Glulam



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	3345 @ 4"	24131 (5.50")	Passed (14%)	--	1.0 D + 1.0 S (All Spans)
Shear (lbs)	2972 @ 1' 4"	14399	Passed (21%)	1.15	1.0 D + 1.0 S (All Spans)
Pos Moment (Ft-lbs)	18901 @ 11' 11 1/2"	27840	Passed (68%)	1.15	1.0 D + 1.0 S (All Spans)
Live Load Defl. (in)	1.178 @ 11' 11 1/2"	1.163	Passed (L/237)	--	1.0 D + 1.0 S (All Spans)
Total Load Defl. (in)	1.569 @ 11' 11 1/2"	1.550	Passed (L/178)	--	1.0 D + 1.0 S (All Spans)

Member Length : 23' 11"  
System : Roof  
Member Type : Drop Beam  
Building Use : Residential  
Building Code : IBC 2018  
Design Methodology : ASD  
Member Pitch : 0/12

- Deflection criteria: LL (L/240) and TL (L/180).
- Allowed moment does not reflect the adjustment for the beam stability factor.
- Volume factor of 0.98 was calculated for positive bending using length L = 23' 3".
- The effects of positive or negative camber have not been accounted for when calculating deflection.
- The specified glulam is assumed to have its strong laminations at the bottom of the beam. Install with proper side up as indicated by the manufacturer.
- Applicable calculations are based on NDS.

Supports	Bearing Length			Loads to Supports (lbs)				Accessories
	Total	Available	Required	Dead	Roof Live	Snow	Factored	
1 - Column - DF	5.50"	5.50"	1.50"	834	837	2511	3345	Blocking
2 - Column - DF	5.50"	5.50"	1.50"	834	837	2511	3345	Blocking

- Blocking Panels are assumed to carry no loads applied directly above them and the full load is applied to the member being designed.

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	23' 11" o/c	
Bottom Edge (Lu)	23' 11" o/c	

- Maximum allowable bracing intervals based on applied load.

Vertical Loads	Location (Side)	Tributary Width	Dead (0.90)	Roof Live (1.25)	Snow (1.15)	Comments
0 - Self Weight (PLF)	0 to 23' 11"	N/A	17.2	--	--	
1 - Uniform (PSF)	0 to 23' 11" (Front)	3' 6"	15.0	20.0	60.0	Default Load

- Side loads are assumed to not induce cross-grain tension.

### Weyerhaeuser Notes


Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to [www.weyerhaeuser.com/woodproducts/document-library](http://www.weyerhaeuser.com/woodproducts/document-library).

The product application, input design loads, dimensions and support information have been provided by ForteWEB Software Operator

ForteWEB Software Operator	Job Notes
Asrade Mengstu Cushing Terrell (406) 500-3544 asrademengstu@cushingterrell.com	

2nd Floor, Roof Beam RB3

1 piece(s) 5 1/2" x 10 1/2" 24F-V4 DF Glulam



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	2766 @ 4"	19663 (5.50")	Passed (14%)	--	1.0 D + 1.0 S (All Spans)
Shear (lbs)	2447 @ 1' 4"	11733	Passed (21%)	1.15	1.0 D + 1.0 S (All Spans)
Pos Moment (Ft-lbs)	12608 @ 7' 3 3/4"	23244	Passed (54%)	1.15	1.0 D + 1.0 S (All Spans)
Live Load Defl. (in)	0.519 @ 8' 9 9/16"	0.863	Passed (L/399)	--	1.0 D + 1.0 S (All Spans)
Total Load Defl. (in)	0.682 @ 8' 9 5/8"	1.150	Passed (L/304)	--	1.0 D + 1.0 S (All Spans)

- Deflection criteria: LL (L/240) and TL (L/180).
- Allowed moment does not reflect the adjustment for the beam stability factor.
- Volume factor of 1.00 was calculated for positive bending using length L = 17' 3".
- The effects of positive or negative camber have not been accounted for when calculating deflection.
- The specified glulam is assumed to have its strong laminations at the bottom of the beam. Install with proper side up as indicated by the manufacturer.
- Applicable calculations are based on NDS.

Member Length : 17' 11"  
System : Roof  
Member Type : Drop Beam  
Building Use : Residential  
Building Code : IBC 2018  
Design Methodology : ASD  
Member Pitch : 0/12

Supports	Bearing Length			Loads to Supports (lbs)				Accessories
	Total	Available	Required	Dead	Roof Live	Snow	Factored	
1 - Column - DF	5.50"	5.50"	1.50"	663	701	2103	2766	Blocking
2 - Column - DF	5.50"	5.50"	1.50"	613	641	1922	2535	Blocking

- Blocking Panels are assumed to carry no loads applied directly above them and the full load is applied to the member being designed.

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	17' 11" o/c	
Bottom Edge (Lu)	17' 11" o/c	

- Maximum allowable bracing intervals based on applied load.

Vertical Loads	Location (Side)	Tributary Width	Dead (0.90)	Roof Live (1.25)	Snow (1.15)	Comments
0 - Self Weight (PLF)	0 to 17' 11"	N/A	14.0	--	--	
1 - Uniform (PSF)	0 to 17' 11" (Front)	3'	15.0	20.0	60.0	Default Load
2 - Point (lb)	7' (Front)	N/A	218	267	800	Linked from: Roof Beam RB1, Support 1

- Side loads are assumed to not induce cross-grain tension.

### Weyerhaeuser Notes


Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to [www.weyerhaeuser.com/woodproducts/document-library](http://www.weyerhaeuser.com/woodproducts/document-library).

The product application, input design loads, dimensions and support information have been provided by ForteWEB Software Operator

ForteWEB Software Operator	Job Notes
Asrade Mengstu Cushing Terrell (406) 500-3544 asrademengstu@cushingterrell.com	

2nd Floor, Roof Beam RB4

**1 piece(s) 5 1/2" x 11 7/8" 24F-V8 DF Glulam**



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	9028 @ 26' 8 1/4"	19701 (5.50")	Passed (46%)	--	1.0 D + 1.0 S (Adj Spans)
Shear (lbs)	4993 @ 27' 10 7/8"	13269	Passed (38%)	1.15	1.0 D + 1.0 S (All Spans)
Pos Moment (Ft-lbs)	14441 @ 14' 4 3/16"	29406	Passed (49%)	1.15	1.0 D + 1.0 S (Alt Spans)
Neg Moment (Ft-lbs)	-11195 @ 26' 8 1/4"	29731	Passed (38%)	1.15	1.0 D + 1.0 S (All Spans)
Live Load Defl. (in)	0.744 @ 14' 3 13/16"	1.225	Passed (L/395)	--	1.0 D + 1.0 S (Alt Spans)
Total Load Defl. (in)	1.067 @ 14' 2 7/16"	1.634	Passed (L/276)	--	1.0 D + 1.0 S (Alt Spans)

Member Length : 29' 7/16"  
System : Roof  
Member Type : Drop Beam  
Building Use : Residential  
Building Code : IBC 2018  
Design Methodology : ASD  
Member Pitch : 0.75/12

- Deflection criteria: LL (L/240) and TL (L/180).
- Overhang deflection criteria: LL (2L/240) and TL (2L/180).
- Upward deflection on left cantilever exceeds overhang deflection criteria.
- Allowed moment does not reflect the adjustment for the beam stability factor.
- Volume factor of 0.99 was calculated for positive bending using length L = 22' 7/8".
- Volume factor of 1.00 was calculated for negative bending using length L = 5' 9 3/16".
- The effects of positive or negative camber have not been accounted for when calculating deflection.
- Applicable calculations are based on NDS.

Supports	Bearing Length			Loads to Supports (lbs)				Accessories
	Total	Available	Required	Dead	Roof Live	Snow	Factored	
1 - Column - DF	5.50"	5.50"	1.50"	966	897	1884	2850	Blocking
2 - Column - DF	5.50"	5.50"	2.52"	2912	2913	6116	9028	Blocking

- Blocking Panels are assumed to carry no loads applied directly above them and the full load is applied to the member being designed.

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	29' o/c	
Bottom Edge (Lu)	29' o/c	

- Maximum allowable bracing intervals based on applied load.
- Dimensions for lateral bracing intervals are measured along the length of the member for sloped conditions.

Vertical Loads	Location (Side)	Tributary Width	Dead (0.90)	Roof Live (1.25)	Snow (1.15)	Comments
0 - Self Weight (PLF)	0 to 28' 11"	N/A	15.9	--	--	
1 - Uniform (PSF)	0 to 14'	3'	18.0	20.0	42.0	Default Load
2 - Uniform (PSF)	14' to 28' 11"	4' 6"	18.0	20.0	42.0	Default Load
3 - Point (lb)	28' 11"	N/A	1450	1549	3253	Linked from: Roof Beam RB5, Support 1

- Side loads are assumed to not induce cross-grain tension.

Forteweb Software Operator	Job Notes
Asrade Mengstu Cushing Terrell (406) 500-3544 asrademengstu@cushingterrell.com	


Weyerhaeuser Notes
Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to <a href="http://www.weyerhaeuser.com/woodproducts/document-library">www.weyerhaeuser.com/woodproducts/document-library</a> .
The product application, input design loads, dimensions and support information have been provided by ForteWEB Software Operator

ForteWEB Software Operator	Job Notes
Asrade Mengstu Cushing Terrell (406) 500-3544 asrademengstu@cushingterrell.com	



2nd Floor, Roof Beam RB5

1 piece(s) 3 1/2" x 11 7/8" 24F-V8 DF Glulam



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	4346 @ 5 1/2"	4346 (1.91")	Passed (100%)	--	1.0 D + 1.0 S (All Spans)
Shear (lbs)	3564 @ 1' 5 3/8"	8444	Passed (42%)	1.15	1.0 D + 1.0 S (All Spans)
Pos Moment (Ft-lbs)	11950 @ 5' 11 1/2"	18920	Passed (63%)	1.15	1.0 D + 1.0 S (All Spans)
Live Load Defl. (in)	0.205 @ 5' 11 1/2"	0.550	Passed (L/645)	--	1.0 D + 1.0 S (All Spans)
Total Load Defl. (in)	0.296 @ 5' 11 1/2"	0.733	Passed (L/446)	--	1.0 D + 1.0 S (All Spans)

- Deflection criteria: LL (L/240) and TL (L/180).
- Allowed moment does not reflect the adjustment for the beam stability factor.
- Volume factor of 1.00 was calculated for positive bending using length L = 11'.
- The effects of positive or negative camber have not been accounted for when calculating deflection.
- Applicable calculations are based on NDS.

Member Length : 11'  
System : Roof  
Member Type : Drop Beam  
Building Use : Residential  
Building Code : IBC 2018  
Design Methodology : ASD  
Member Pitch : 0/12

Supports	Bearing Length			Loads to Supports (lbs)				Accessories
	Total	Available	Required	Dead	Roof Live	Snow	Factored	
1 - Hanger on 11 7/8" GLB beam	5.50"	Hanger <sup>1</sup>	1.91"	1450	1549	3253	4703	See note <sup>1</sup>
2 - Hanger on 11 7/8" GLB beam	5.50"	Hanger <sup>1</sup>	1.91"	1450	1549	3253	4703	See note <sup>1</sup>

• At hanger supports, the Total Bearing dimension is equal to the width of the material that is supporting the hanger

• <sup>1</sup> See Connector grid below for additional information and/or requirements.

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	11' o/c	
Bottom Edge (Lu)	11' o/c	

•Maximum allowable bracing intervals based on applied load.

#### Connector: Simpson Strong-Tie

Support	Model	Seat Length	Top Fasteners	Face Fasteners	Member Fasteners	Accessories
1 - Face Mount Hanger	HHUS48	3.00"	N/A	22-16d	8-16d	
2 - Face Mount Hanger	HHUS48	3.00"	N/A	22-16d	8-16d	

• Refer to manufacturer notes and instructions for proper installation and use of all connectors.

Vertical Loads	Location (Side)	Tributary Width	Dead (0.90)	Roof Live (1.25)	Snow (1.15)	Comments
0 - Self Weight (PLF)	5 1/2" to 11' 5 1/2"	N/A	10.1	--	--	
1 - Uniform (PSF)	0 to 11' 11" (Front)	13'	18.0	20.0	42.0	Default Load

• Side loads are assumed to not induce cross-grain tension.

#### Weyerhaeuser Notes


Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to [www.weyerhaeuser.com/woodproducts/document-library](http://www.weyerhaeuser.com/woodproducts/document-library).

The product application, input design loads, dimensions and support information have been provided by ForteWEB Software Operator

ForteWEB Software Operator	Job Notes
Asrade Mengstu Cushing Terrell (406) 500-3544 asrademengstu@cushingterrell.com	

2nd Floor, Roof Beam RB6

1 piece(s) 5 1/2" x 11 7/8" 24F-V8 DF Glulam



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	6232 @ 26' 8 1/4"	19701 (5.50")	Passed (32%)	--	1.0 D + 1.0 S (Adj Spans)
Shear (lbs)	4780 @ 27' 10 7/8"	13269	Passed (36%)	1.15	1.0 D + 1.0 S (All Spans)
Pos Moment (Ft-lbs)	2631 @ 10' 9 3/16"	29731	Passed (9%)	1.15	1.0 D + 1.0 S (Alt Spans)
Neg Moment (Ft-lbs)	-10672 @ 26' 8 1/4"	29731	Passed (36%)	1.15	1.0 D + 1.0 S (All Spans)
Live Load Defl. (in)	0.148 @ 28' 11"	0.223	Passed (2L/362)	--	1.0 D + 1.0 S (Alt Spans)
Total Load Defl. (in)	0.174 @ 28' 11"	0.298	Passed (2L/308)	--	1.0 D + 1.0 S (Alt Spans)

Member Length : 29' 7/16"  
System : Roof  
Member Type : Drop Beam  
Building Use : Residential  
Building Code : IBC 2018  
Design Methodology : ASD  
Member Pitch : 0.75/12

- Deflection criteria: LL (L/240) and TL (L/180).
- Overhang deflection criteria: LL (2L/240) and TL (2L/180).
- Allowed moment does not reflect the adjustment for the beam stability factor.
- Volume factor of 1.00 was calculated for positive bending using length L = 16' 8 3/16".
- Volume factor of 1.00 was calculated for negative bending using length L = 13' 11 3/16".
- The effects of positive or negative camber have not been accounted for when calculating deflection.
- Applicable calculations are based on NDS.

Supports	Bearing Length			Loads to Supports (lbs)				Accessories
	Total	Available	Required	Dead	Roof Live	Snow	Factored	
1 - Column - DF	5.50"	5.50"	1.50"	359	220	461	820	Blocking
2 - Column - DF	5.50"	5.50"	1.74"	2073	1980	4159	6232	Blocking

- Blocking Panels are assumed to carry no loads applied directly above them and the full load is applied to the member being designed.

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	29' o/c	
Bottom Edge (Lu)	29' o/c	

- Maximum allowable bracing intervals based on applied load.
- Dimensions for lateral bracing intervals are measured along the length of the member for sloped conditions.

Vertical Loads	Location (Side)	Tributary Width	Dead (0.90)	Roof Live (1.25)	Snow (1.15)	Comments
0 - Self Weight (PLF)	0 to 28' 11"	N/A	15.9	--	--	
1 - Uniform (PSF)	0 to 28' 11"	1'	18.0	20.0	42.0	Default Load
2 - Point (lb)	28' 11"	N/A	1450	1549	3253	Linked from: Roof Beam RB5, Support 2

- Side loads are assumed to not induce cross-grain tension.

#### Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to [www.weyerhaeuser.com/woodproducts/document-library](http://www.weyerhaeuser.com/woodproducts/document-library).

The product application, input design loads, dimensions and support information have been provided by ForteWEB Software Operator

ForteWEB Software Operator	Job Notes
Asrade Mengstu Cushing Terrell (406) 500-3544 asrademengstu@cushingterrell.com	



SEARCH C WRANGELL - STAFF HOUSING - 1064 ZIMOVIA HWY  
WRANGELL AK 99929

SINGLE FAMILY TWO STORY (SHED ROOF)

## LATERAL ANALYSIS

### WIND ANALYSIS

$V = 139 \text{ mph}$ , Exp 'D',  $K_{zt} = 1.0$

SEE ATTACHED WIND PRESSURE CALCULATIONS (STRUWARE)

→ WIND IN N-S DIRECTION:

$$\text{ROOF} = 175 \times 30.3 = 5,302.5 \#$$

$$2^{\text{nd}} \text{ FL} = 276 \times 29.4 = 8,114.4 \#$$

$$\text{TOTAL} = 13,417 \#$$

→ WIND IN E-W DIRECTION:

$$\text{ROOF} = 153 \times 30.3 = 4,636 \#$$

$$2^{\text{nd}} \text{ FL} = 396 \times 29.4 = 11,642.4 \#$$

$$\text{TOTAL} = 16,278 \#$$

### SEISMIC ANALYSIS

SEISMIC DEAD LOAD:

$$\text{ROOF DL} = 714 \times 18 + 2(25 + 20.5) \times 5' \times 15$$

$$= 12,852 + 6,825 = 19,677 \#$$

$$2^{\text{nd}} \text{ FL DL} = (239 + 623) \times 18 \text{ psf} + 518 \times 15 + 2(26 + 41) \times 9.5' \times 15 \text{ psf}$$

$$= 15,516 + 7,770 + 19,095 = 42,381 \#$$

$$\text{TOTAL} = 62,058 \#$$

FROM ATTACHED CALCULATIONS,  $V = 0.021$   $W = 1.3k$

⇒ WIND GOVERNS BOTH DIRECTIONS.



# ASCE Hazards Report

**Address:**  
No Address at This Location

**Standard:** ASCE/SEI 7-16  
**Risk Category:** II  
**Soil Class:** B - Rock

**Latitude:** 56.460443  
**Longitude:** -132.376976  
**Elevation:** 96.81758915131236 ft (NAVD 88)



## Wind

### Results:

Wind Speed	139 Vmph
10-year MRI	98 Vmph
25-year MRI	106 Vmph
50-year MRI	113 Vmph
100-year MRI	119 Vmph

**Data Source:** ASCE/SEI 7-16, Fig. 26.5-1B and Figs. CC.2-1–CC.2-4, and Section 26.5.2  
**Date Accessed:** Mon Aug 18 2025

Value provided is 3-second gust wind speeds at 33 ft above ground for Exposure C Category, based on linear interpolation between contours. Wind speeds are interpolated in accordance with the 7-16 Standard. Wind speeds correspond to approximately a 7% probability of exceedance in 50 years (annual exceedance probability = 0.00143, MRI = 700 years).





Site is not in a hurricane-prone region as defined in ASCE/SEI 7-16 Section 26.2.



**Site Soil Class:** B - Rock

**Results:**

$S_S$ :	0.249	$S_{D1}$ :	0.136
$S_1$ :	0.254	$T_L$ :	12
$F_a$ :	0.9	PGA :	0.093
$F_v$ :	0.8	PGA <sub>M</sub> :	0.083
$S_{MS}$ :	0.224	$F_{PGA}$ :	0.9
$S_{M1}$ :	0.204	$I_e$ :	1
$S_{DS}$ :	0.149	$C_v$ :	0.749



**Data Accessed:** Mon Aug 18 2025

**Date Source:**

USGS Seismic Design Maps based on ASCE/SEI 7-16 and ASCE/SEI 7-16 Table 1.5-2. Additional data for site-specific ground motion procedures in accordance with ASCE/SEI 7-16 Ch. 21 are available from USGS.

**Results:**

Ground Snow Load, $p_g$ :	60 lb/ft <sup>2</sup>
Mapped Elevation:	96.8 ft
Data Source:	ASCE/SEI 7-16, Table 7.2-8
Date Accessed:	Mon Aug 18 2025

Values provided are ground snow loads. In areas designated "case study required," extreme local variations in ground snow loads preclude mapping at this scale. Site-specific case studies are required to establish ground snow loads at elevations not covered.

Snow load values are mapped to a 0.5 mile resolution. This resolution can create a mismatch between the mapped elevation and the site-specific elevation in topographically complex areas. Engineers should consult the local authority having jurisdiction in locations where the reported 'elevation' and 'mapped elevation' differ significantly from each other.

---

The ASCE Hazard Tool is provided for your convenience, for informational purposes only, and is provided "as is" and without warranties of any kind. The location data included herein has been obtained from information developed, produced, and maintained by third party providers; or has been extrapolated from maps incorporated in the ASCE standard. While ASCE has made every effort to use data obtained from reliable sources or methodologies, ASCE does not make any representations or warranties as to the accuracy, completeness, reliability, currency, or quality of any data provided herein. Any third-party links provided by this Tool should not be construed as an endorsement, affiliation, relationship, or sponsorship of such third-party content by or from ASCE.

ASCE does not intend, nor should anyone interpret, the results provided by this Tool to replace the sound judgment of a competent professional, having knowledge and experience in the appropriate field(s) of practice, nor to substitute for the standard of care required of such professionals in interpreting and applying the contents of this Tool or the ASCE standard.

In using this Tool, you expressly assume all risks associated with your use. Under no circumstances shall ASCE or its officers, directors, employees, members, affiliates, or agents be liable to you or any other person for any direct, indirect, special, incidental, or consequential damages arising from or related to your use of, or reliance on, the Tool or any information obtained therein. To the fullest extent permitted by law, you agree to release and hold harmless ASCE from any and all liability of any nature arising out of or resulting from any use of data provided by the ASCE Hazard Tool.

# SEISMIC BASE SHEAR: ASCE 7-16

Occupancy Category = 1  
Site Class = B  
Lat. = 56.460  
Long. = -132.377  
Ss = 24.9 % g  
S1 = 25.4 % g

Seismic Design Category (SDC) = C  
Fa = 0.900  
Fv = 0.8  
Sds = 0.149  
Sd1 = 0.135

Vmin = 0.044\*Sds W : 0.01  
V = Sds\*I W : 0.02  
R  
Vmax = Sd1\*I W : 0.10  
R\*T

Where: Sds = 0.149  
Sd1 = 0.135  
I = 1  
R = 6.5

## WOOD SW

Therefore: V.ult = 0.023 W V = 1.4 kips  
V.service = 0.016 W V = 1.0 kips

E = ρ Eh + Ev  
where

ρ = 1.0 or 1.3  
ρ.y = 1.3  
ρ.x = 1.3

## INCREASE SEISMIC

V.ult = 0.030 W V = 1.9 kips  
V.service = 0.021 W V = 1.3 kips

Note: IBC Ax and r are evaluated at each floor

Therefore: pEx = 1.9 kips pEy = 1.9 kips  
pEx = 1.3 kips pEy = 1.3 kips

static distribution is relative to T = 0.203 sec -----> linear  
distributing period distribution -----> k (exponent) = 1.00

## SEISMIC DISTRIBUTION: X-Direction

level	W (kips)	h (ft)	Wh <sup>k</sup> (kip-ft)	STRENGTH / LRFD		ALLOW. STRESS DESIGN		Diaphragm	
				Wh <sup>k</sup> Σ Wh <sup>k</sup>	story shear Σ (kips)	story shear Σ (kips)	Σ (kips)	Scaled Seismic (kips)	Scaled Seismic
Roof	19.7	20	394	0.48	0.9	0.9	0.6	0.008	0.2
2nd Floor	42.4	10	424	0.52	1.0	1.9	0.7	0.004	0.2
Σ	62.1		818	1	1.9		1.3	0.3	
							.7E	.7E	.7E

## SEISMIC DISTRIBUTION: Y-Direction

level	W (kips)	h (ft)	Wh <sup>k</sup> (kip-ft)	STRENGTH / LRFD		ALLOW. STRESS DESIGN		Diaphragm	
				Wh <sup>k</sup> Σ Wh <sup>k</sup>	story shear Σ (kips)	story shear Σ (kips)	Σ (kips)	Scaled Seismic (kips)	Scaled Seismic
Roof	19.7	20	394	0.48	0.9	0.9	0.6	0.008	0.2
2nd Floor	42.4	10	424	0.52	1.0	1.9	0.7	0.004	0.2
Σ	62.1		818	1	1.9		1.3	0.3	
							.7E	.7E	.7E

# SEARHC WRANGELL - 2bd2stryShed

Fa	Ss				
	Ss <	Ss =	Ss =	Ss =	Ss >
A	0.25	0.5	0.75	1	1.25
B	0.8	0.8	0.8	0.8	0.8
C	1	1	1	1	1
D	1.2	1.2	1.1	1	1
E	1.6	1.4	1.2	1.1	1
F	2.5	1.7	1.2	0.9	0.9
	a	a	a	a	a
Fv	S1				
	S1 <	S1 =	S1 =	S1 =	S1 >
A	0.1	0.2	0.3	0.4	0.5
B	0.8	0.8	0.8	0.8	0.8
C	1	1	1	1	1
D	1.7	1.6	1.5	1.4	1.3
E	2.4	2	1.8	1.6	1.5
F	3.5	3.2	2.8	2.4	2.4
	a	a	a	a	a

T exponen	Ct
0.75	0.02 default
0.75	0.03 Ecc Braced Frames
0.8	0.016 Concrete Moment Frames
0.9	0.028 Steel Moment Frames

Common Values		
	R	omega
Wood SW	6.5	3 bearing wall system
Special Conc SW	5	2.5 bearing wall system
Special CMU SW	5	2.5 bearing wall system
Steel OMRF	3.5	3 building frame system
Steel SMRF	8	3 building frame system
Steel OBF	5	2 building frame system
Steel SBF	6	2 building frame system
Cant Col		building frame system

## STRUCTURAL CALCULATIONS

FOR

**SEARHC Wrangell - Staff Housing**

Wrangell, Alaska

## Code Search

**Code:** International Building Code 2021

### **Occupancy:**

Occupancy Group = R Residential

### **Risk Category & Importance Factors:**

Risk Category = II

Wind factor = 1.00 use 0.60 NOTE: Output will be nominal wind pressures

Snow factor = 1.00

Seismic factor = 1.00

### **Type of Construction:**

Fire Rating:

Roof = 1.0 hr

Floor = 1.0 hr

### **Building Geometry:**

Roof angle ( $\theta$ ) 0.75 / 12 3.6 deg

Building length 41.0 ft

Least width 26.0 ft

Mean Roof Ht (h) 21.0 ft

Parapet ht above grd 0.0 ft

Minimum parapet ht 0.0 ft

### **Live Loads:**

**Roof** 0 to 200 sf: 20 psf

200 to 600 sf: 24 - 0.02Area, but not less than 12 psf

over 600 sf: 12 psf

### **Floor:**

Typical Floor 40 psf

Partitions N/A

0 psf

0 0 psf

Stairs and exit ways 100 psf

## Wind Loads :

ASCE 7- 16

Ultimate Wind Speed	139 mph
Nominal Wind Speed	107.7 mph
Risk Category	II
Exposure Category	D
Enclosure Classif.	Enclosed Building
Internal pressure	+/-0.18
Directionality (Kd)	0.85
Kh case 1	1.092
Kh case 2	1.092
Type of roof	Monoslope

### Topographic Factor (Kzt)

Topography	2D Escarpment
Hill Height (H)	20.0 ft
Half Hill Length (Lh)	300.0 ft
Actual H/Lh	= 0.07
Use H/Lh	= 0.00
Modified Lh	= 300.0 ft
From top of crest: x =	50.0 ft
Bldg up/down wind?	downwind

$$H/Lh = 0.00 \quad K_1 = 0.000$$


$$x/Lh = 0.17 \quad K_2 = 0.958$$

$$z/Lh = 0.07 \quad K_3 = 0.839$$


At Mean Roof Ht:

$$K_{zt} = (1 + K_1 K_2 K_3)^2 = 1.00$$

$$H/Lh < 0.2 \\ \therefore K_{zt} = 1.0$$



**ESCARPMENT**



**2D RIDGE or 3D AXISYMMETRICAL HILL**

## Gust Effect Factor

h =	21.0 ft
B =	26.0 ft
/z (0.6h) =	12.6 ft

Flexible structure if natural frequency < 1 Hz (T > 1 second).

If building h/B > 4 then may be flexible and should be investigated.

$$h/B = 0.81 \quad \text{Rigid structure (low rise bldg)}$$

$$G = 0.85 \quad \text{Using rigid structure default}$$

### Rigid Structure

$\bar{e}$ =	0.13
$\ell$ =	650 ft
$z_{min}$ =	7 ft
c =	0.15
$g_Q, g_v$ =	3.4
$L_z$ =	576.3 ft
Q =	0.94
$I_z$ =	0.18
G =	0.90 use G = 0.85

### Flexible or Dynamically Sensitive Structure

Natural Frequency ( $\eta_1$ ) =	0.0 Hz		
Damping ratio ( $\beta$ ) =	0		
$/b$ =	0.80		
$/\alpha$ =	0.11		
$V_z$ =	146.5		
$N_1$ =	0.00		
$R_n$ =	0.000		
$R_h$ =	28.282	$\eta =$	0.000
$R_B$ =	28.282	$\eta =$	0.000
$R_L$ =	28.282	$\eta =$	0.000
$g_R$ =	0.000		
R =	0.000		
Gf =	0.000		
		h =	21.0 ft

## Enclosure Classification

**Test for Enclosed Building:**  $A_o < 0.01A_g$  or 4 sf, whichever is smaller

**Test for Open Building:** All walls are at least 80% open.  
 $A_o \geq 0.8A_g$

**Test for Partially Enclosed Building:** Predominately open on one side only

Input		Test	
Ao	500.0 sf	$A_o \geq 1.1A_{oi}$	NO
Ag	600.0 sf	$A_o > 4'$ or $0.01A_g$	YES
Aoi	1000.0 sf	$A_{oi} / A_{gi} \leq 0.20$	YES
Agi	10000.0 sf		

Building is NOT Partially Enclosed

Conditions to qualify as Partially Enclosed Building. Must satisfy all of the following:

$A_o \geq 1.1A_{oi}$

$A_o >$  smaller of 4' or 0.01 Ag

$A_{oi} / A_{gi} \leq 0.20$

Where:

$A_o$  = the total area of openings in a wall that receives positive external pressure.

$A_g$  = the gross area of that wall in which  $A_o$  is identified.

$A_{oi}$  = the sum of the areas of openings in the building envelope (walls and roof) not including  $A_o$ .

$A_{gi}$  = the sum of the gross surface areas of the building envelope (walls and roof) not including  $A_g$ .

**Test for Partially Open Building:** A building that does not qualify as open, enclosed or partially enclosed.  
(This type building will have same wind pressures as an enclosed building.)

## Reduction Factor for large volume partially enclosed buildings (Ri) :

If the partially enclosed building contains a single room that is unpartitioned , the internal pressure coefficient may be multiplied by the reduction factor Ri.

Total area of all wall & roof openings ( $A_{og}$ ): 0 sf

Unpartitioned internal volume ( $V_i$ ) : 0 cf

Ri = 1.00

## Ground Elevation Factor (Ke)

Grd level above sea level = 0.0 ft

Constant = 0.00256

Adj Constant = 0.00256

Ke = 1.0000

## Wind Loads - MWFRS all h (Except for Open Buildings)

Kh (case 2) =	1.09			GCpi =	+/-0.18
Base pressure (qh) =	27.6 psf	Bldg dim parallel to ridge =	41.0 ft	G =	0.85
Roof Angle (θ) =	3.6 deg	Bldg dim normal to ridge =	26.0 ft	qi = qh	
Roof tributary area:		h =	21.0 ft		
Wind normal to ridge =(h/2)*L:	431 sf	ridge ht =	21.8 ft		
Wind parallel to ridge =(h/2)*L:	273 sf				

### Nominal Wind Surface Pressures (psf)

Surface	Wind Normal to Ridge				Wind Parallel to Ridge			
	L/B = 0.63		h/L = 0.81		L/B = 1.58		h/L = 0.51	
	Cp	qhGCp	w/+qiGCpi	w/-qhGCpi	Dist.*	Cp	qhGCp	w/+qiGCpi w/-qhGCpi
Windward Wall (WW)	0.80	18.7	see table below			0.80	18.7	see table below
Leeward Wall (LW)	-0.50	-11.7	-16.7	-6.8		-0.38	-9.0	-14.0 -4.0
Side Wall (SW)	-0.70	-16.4	-21.4	-11.4		-0.70	-16.4	-21.4 -11.4
Leeward Roof (LR)	**				Included in windward roof			
Neg Windward Roof: 0 to h/2*	-1.04	-24.4	-29.4	-19.5	0 to h/2*	-0.91	-21.2	-26.2 -16.3
h/2 to h*	-0.78	-18.2	-23.2	-13.2	h/2 to h*	-0.90	-21.0	-25.9 -16.0
h to 2h*	-0.62	-14.6	-19.6	-9.6	h to 2h*	-0.50	-11.8	-16.8 -6.9
Pos/min windward roof press.	-0.18	-4.2	-9.2	0.7	Min press.	-0.18	-4.2	-9.2 0.7

\*\*Roof angle < 10 degrees. Therefore, leeward roof is included in windward roof pressure zones.

\*Horizontal distance from windward edge

For monoslope roofs, entire roof surface is either windward or leeward surface.

### Parapet

z	Kz	Kzt	qp (psf)
0.0 ft	1.03	1.00	0.0


Windward parapet: 0.0 psf (GCpn = +1.5)

Leeward parapet: 0.0 psf (GCpn = -1.0)


Windward roof overhangs : 18.7 psf (upward - add to windward roof pressure)

### Windward Wall Pressures at "z" (psf)


z	Kz	Kzt	Windward Wall			Combined WW + LW	
			qzGCp	w/+qiGCpi	w/-qhGCpi	Wind Normal to Ridge	Wind Parallel to Ridge
0 to 15'	1.03	1.00	17.7	12.7	22.6	29.4	26.7
20.0 ft	1.08	1.00	18.6	13.6	23.5	30.3	27.6
h= 21.0 ft	1.09	1.00	18.7	13.8	23.7	30.4	27.7
ridge = 21.8 ft	1.10	1.00	18.9	13.9	23.8	30.6	27.9



WIND NORMAL TO RIDGE




WIND PARALLEL TO RIDGE



TYPICAL WIND LOADING



NOTE: ASCE 7 requires the application of full and partial loading of the wind pressures per the 4 cases below.



### Wind Forces at Floors

Total Floors = 1  
T/Fdn (dist below grade) = 2.0 ft

Building dimension (parallel with ridge) = 41.0 ft  
Building dimension (normal to ridge) = 26.0 ft  
L is the building dimension parallel to the wind direction

e = 6.15 ft  
e = 3.90 ft

Level	Elevation Above Grade (ft)	Height of Centroid to Fdn (ft)	Wind Normal to Ridge						Wind Parallel to Ridge			
			L	B	Area (sf)	Applied Force (k)	Story Shear (k)	Overturning Moment (k)	Area	Applied Force (k)	Story Shear (k)	Overturning Moment (k)
Equip, etc		0.00	wind on equip, screenwalls, etc =									0.0
Parapet	0.00	0.00				0.0		0.0		0.0		0.0
T/Ridge	0.00	0.00			0.0	0.0		0.0	0.0	0.0		0.0
Roof	15.00	17.00	26.0	41.0	307.5	9.0	9.0	0.0	195.0	5.2	5.2	0.0
1	0.00	2.00	26.0	41.0	307.5	9.0	18.1	135.5	195.0	5.2	10.4	78.0
FDN		0.00						171.7				98.8

## Nominal Wind Pressures

### Wind Loads - Components & Cladding : $h \leq 60'$

Kh (case 2) = 1.09 h = 21.0 ft  
Base pressure (qh) = **27.6 psf** a = 3.0 ft  
Minimum parapet ht = 0.0 ft GCpi = +/-0.18  
Roof Angle ( $\theta$ ) = 3.6 deg qi = qh = 27.6 psf  
Type of roof = Monoslope

#### Roof

Area	GCp +/- GCpi				Surface Pressure (psf)			
	10 sf	20 sf	50 sf	100 sf	10 sf	20 sf	50 sf	100 sf
Negative Zone 1	-1.28	-1.28	-1.28	-1.28	-35.3	-35.3	-35.3	-35.3
Negative Zone 2	-1.48	-1.45	-1.41	-1.38	-40.8	-40.0	-38.9	-38.0
Negative Zone 2'	-1.78	-1.75	-1.71	-1.68	-49.0	-48.2	-47.1	-46.3
Negative Zone 3	-1.98	-1.8	-1.56	-1.38	-54.6	-49.6	-43.0	-38.0
Negative Zone 3'	-2.78	-2.48	-2.08	-1.78	-76.6	-68.3	-57.3	-49.0
Positive All Zones	0.48	0.45	0.41	0.38	13.2	12.4	11.3	10.5

User input	
75 sf	150 sf
-35.3	-35.3
-38.4	-38.0
-46.6	-46.3
-40.1	-38.0
-52.5	-49.0
10.8	10.5

#### Parapet

qp = 0.0 psf

		Surface Pressure (psf)					
Solid Parapet Pressure		10 sf	20 sf	50 sf	100 sf	200 sf	500 sf
CASE A:	Zone 2 :	0.0	0.0	0.0	0.0	0.0	0.0
	Zone 2' :	0.0	0.0	0.0	0.0	0.0	0.0
	Zone 3 :	0.0	0.0	0.0	0.0	0.0	0.0
	Zone 3' :	0.0	0.0	0.0	0.0	0.0	0.0
CASE B:	Interior zone :	0.0	0.0	0.0	0.0	0.0	0.0
	Corner zone :	0.0	0.0	0.0	0.0	0.0	0.0

User input	
40 sf	
0.0	
0.0	
0.0	
0.0	
0.0	


#### Walls

Area	GCp +/- GCpi				Surface Pressure at h			
	10 sf	100 sf	200 sf	500 sf	10 sf	100 sf	200 sf	500 sf
Negative Zone 4	-1.17	-1.01	-0.96	-0.90	-32.2	-27.9	-26.5	-24.8
Negative Zone 5	-1.44	-1.12	-1.03	-0.90	-39.7	-30.9	-28.3	-24.8
Positive Zone 4 & 5	1.08	0.92	0.87	0.81	29.8	25.4	24.1	22.3


User input	
50 sf	300 sf
-29.2	-25.8
-33.6	-26.7
26.7	23.3

Note: GCp reduced by 10% due to roof angle  $\leq 10$  deg.


## Location of C&C Wind Pressure Zones - ASCE 7-16




Roofs w/  $\theta \leq 10^\circ$   
and all walls  
 $h > 60'$




Walls  $h \leq 60'$   
& alt design  $h < 90'$




Gable, Sawtooth and  
Multispan Gable  $\theta \leq 7$  degrees &  
Monoslope  $\leq 3$  degrees  
 $h \leq 60'$  & alt design  $h < 90'$




Monoslope roofs  
 $3^\circ < \theta \leq 10^\circ$   
 $h \leq 60'$  & alt design  $h < 90'$





Monoslope roofs  
 $10^\circ < \theta \leq 30^\circ$   
 $h \leq 60'$  & alt design  $h < 90'$




Multispan Gable &  
Gable  $7^\circ < \theta \leq 45^\circ$




Hip  $7^\circ < \theta \leq 27^\circ$



Sawtooth  $10^\circ < \theta \leq 45^\circ$   
 $h \leq 60'$  & alt design  $h < 90'$




Stepped roofs  $\theta \leq 3^\circ$   
 $h \leq 60'$  & alt design  $h < 90'$




Note: The stepped roof zones above are as shown in ASCE 7-16 (except the upper roof zones 1 and 2 are shown at the inside edge per the notes). Prior editions didn't show zones, but the notes sent you to the low slope gable figure. The note in ASCE 7-16 still sends you to the low slope gable figure, but for some reasons the zones shown are per editions prior to ASCE 7-16. Therefore, the above zones may be a code mistake and the correct zone locations may be per the low slope gable roof shown at the top of this page.


## Location of C&C Wind Pressure Zones - ASCE 7-10 & earlier




Roofs w/  $\theta \leq 10^\circ$   
and all walls  
 $h > 60'$




Walls  $h \leq 60'$   
& alt design  $h < 90'$




Gable, Sawtooth and  
Multispan Gable  $\theta \leq 7^\circ$  degrees &  
Monoslope  $\leq 3^\circ$  degrees  
 $h \leq 60'$  & alt design  $h < 90'$




Monoslope roofs  
 $3^\circ < \theta \leq 10^\circ$   
 $h \leq 60'$  & alt design  $h < 90'$





Monoslope roofs  
 $10^\circ < \theta \leq 30^\circ$   
 $h \leq 60'$  & alt design  $h < 90'$




Multispan Gable &  
Gable  $7^\circ < \theta \leq 45^\circ$




Hip  $7^\circ < \theta \leq 27^\circ$



Sawtooth  $10^\circ < \theta \leq 45^\circ$   
 $h \leq 60'$  & alt design  $h < 90'$



Stepped roofs  $\theta \leq 3^\circ$   
 $h \leq 60'$  & alt design  $h < 90'$



**SEARHC WRANGELL 2bd2stryShed**

V in N-S Roof  
shear (k) = 5.30 (Wind)

Wall	TW (ft)	V (k)	L (ft)	v (plf)	SW Type	h (ft)	Mot (k-ft)	TW (ft)	DLroof (psf)	Wfl (plf)	DLwall (psf)	Wwall (plf)	Mr (k-ft)	.6Mr (k-ft)	FS	T (lbs)	Holdowns	Wall
1	12.5	2.65	6.5	408	SWB													1
3	12.5	2.65	9.5	279	SWB													3
25																		

\* Shearwall capacity reduced by 1.25-0.125h/b

V in N-S 2nd Floor  
shear (k) = 13.40 (Wind)

Wall	TW (ft)	V (k)	L (ft)	v (plf)	SW Type	h (ft)	Mot (k-ft)	TW (ft)	DLfloor (psf)	Wfl (plf)	DLwall (psf)	Wwall (plf)	Mr (k-ft)	.6Mr (k-ft)	FS	T (lbs)	Holdowns	Wall
1	12.5	6.70	10.75	623	SWC													1
3	12.5	6.70	21	319	SWB													3
25																		

\* Shearwall capacity reduced by 1.25-0.125h/b

**Holdowns**

V in N-S		Roof		Mot (k-ft)	TW (ft)	DLfloor (psf)	Wfl (plf)	DLwall (psf)	Wwall (plf)	Mr (k-ft)	.6Mr (k-ft)	FS	<b>T (lbs)</b>	Holdowns	Wall	<b>C (lbs)</b>
Wall	v=	L (ft)	h (ft)													
		408	plf													
1		6.5	10	26.50	8.5	18	153	10	100	5	3.2	0.12	3584	48	1	4077
	v=	279	plf													
3		9.5	10	26.50	7.5	18	135	10	100	11	6.4	0.24	2120	37	3	2789
V in N-S		2nd Floor		Mot (k-ft)	TW (ft)	DLfloor (psf)	Wfl (plf)	DLwall (psf)	Wwall (plf)	Mr (k-ft)	.6Mr (k-ft)	FS	<b>T (lbs)</b>	Holdowns	Wall	<b>C (lbs)</b>
Wall	v=	L (ft)	h (ft)													
		623	plf													
1a		5.5	10	34.28	6.5	15	97.5	10	100	3	1.8	0.05	5907	8	1a	6233
1b		5.25	10	32.72	6.5	15	97.5	10	100	3	1.6	0.05	5921	8	1b	6233
	v=	319	plf													
3		21	9	86.80	10	18	180	10	90	70	42.1	0.48	2129	4	3	4133

SEARHC WRANGELL 2bd2stryShed

V in E-W		Roof																	
		shear (k) =		4.64	(Wind)														
Wall	TW (ft)	V (k)	L (ft)	v (plf)	SW Type	h (ft)	Mot (k-ft)	TW (ft)	DLfloor(psf)	Wfl (plf)	DLwall (psf)	Wwall (plf)	Mr (k-ft)	.6Mr (k-ft)	FS	T (lbs)	Holdowns	Wall	
C	10.5	2.32	11	211	SWA													C	
D	10.5	2.32	12.25	189	SWA													D	
		21																	

**Holdowns**

V in E-W	Roof															
Wall	L (ft)	h (ft)	Mot (k-ft)	TW (ft)	DLroof (psf)	Wfl (plf)	DLwall (psf)	Wwall (plf)	Mr (k-ft)	.6Mr (k-ft)	FS	T (lbs)	Holdowns	Wall	C (lbs)	
v=	211	plf														
C1	6.75	10	14.24	3	18	54	10	100	4	2.1	0.15	1797	37	C1	2109	
C2	4.25	10	8.96	3	18	54	10	100	1	0.8	0.09	1913	37	C2	2109	
v=	189	plf														
D	15.25	10	28.88	3	18	54	10	100	18	10.7	0.37	1189	37	D	1894	
V in E-W	2nd Floor															
Wall	L (ft)	h (ft)	Mot (k-ft)	TW (ft)	DLroof (psf)	Wfl (plf)	DLwall (psf)	Wwall (plf)	Mr (k-ft)	.6Mr (k-ft)	FS	T (lbs)	Holdowns	Wall	C (lbs)	
v=	407	plf														
C1	9	9	32.97	1	15	15	10	90	4	2.6	0.08	3380	4	C1	3663	
C2	9.5	9	43.76	1	15	15	10	90	6	3.7	0.08	4219	4	C2	4607	
v=	229	plf														
D	17.75	9	93.90	3	15	45	10	90	39	23.5	0.25	3966	4	D	5290	
v=	836	plf														
B1	2.6	9	19.56	3.5	22	77	10	90	1	0.3	0.02	7392	8	B1	7522	
B2	3	9	22.57	6.5	22	143	10	90	1	0.6	0.03	7313	8	B2	7522	